

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20186-00-00
Spot: NENW Sec/Twnshp/Rge: 16-1S-18W
660 feet from N Section Line, 1980 feet from W Section Line
Lease/Unit Name: FLORY Well Number: 2
County: PHILLIPS Total Vertical Depth: 3582 feet

Operator License No.: 31070 Conductor Pipe: Size feet:
Op Name: EAGLE RIVER ENERGY CORPORATION Surface Casing: Size 8.62 feet: 250 175 SX CMT
Address: 7060 S. YALE #609 Production: Size 5.5 feet: 3580 250 SX CMT \$116.42
TULSA, OK 74136 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/15/2001 10:00 PM
Plug Co. License No.: 31070 Plug Co. Name: EAGLE RIVER ENERGY CORPORATION
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (918) 494-8928

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
T.O.F. - 450' est. Casing leak at 990'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 01/15/2001 2:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing to 1600'. Spotted 120 sxs cement with 400# hulls to circulate at surface.
Pulled tubing and squeezed casing with 30 sxs cement.
Max. P.S.I. 300#. S.I.P. 100#.
RU Cementers to 8 5/8" S.P.
Squeezed 50 sxs cement with 100# hulls.
Max. P.S.I. 300#. S.I.P. 200#.

INVOICED
DATE 03-07-2001
INV. NO. 2001061401

Remarks: ALLIED CEMENTING COMPANY - RUSSELL, KANSAS.

Plugged through: TBG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

FEB 06 2001

