

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-19003-00-00
Spot: CN2SE Sec/Twnshp/Rge: 17-1S-18W
1980 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: LUTJEHARM Well Number: 3
County: PHILLIPS Total Vertical Depth: 3540 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATION
Address: 7060 S. YALE #609
TULSA, OK 74136

Conductor Pipe: Size feet: 8 115.05
Surface Casing: Size 8.625 feet: 212 150 SX CMT
Production: Size 4.5 feet: 3537 175 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/11/2002 8:00 AM

Plug Co. License No.: 31070 Plug Co. Name: EAGLE RIVER ENERGY CORPORATION

Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (316) 793-2645

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
W.L.M. 1000'.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 03/11/2002 1:45 PM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing to 1800'.
Spotted 50 sxs cement with 300# hulls.
Pulled to 900'.
Spotted 100 sxs cement with 100# hulls.
POOH with tubing.
Squeezed 4 1/2" casing with 25 sxs cement to Max. P.S.I. 500#.
8 5/8" S.P. - Squeezed 25 sxs cement down annulus.
Max. P.S.I. 300#.

RECEIVED
MAR 29 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis J. Hamel

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE March 29-02

INV. NO. 2002061584

MAR 27 2002

