

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20382-00-00
Spot: SESWNW Sec/Twnshp/Rge: 3-29S-32W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: HOLLOWAY Well #: 1
County: HASKELL Total Vertical Depth: 5575 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

PROD Size: 4.5 feet: 5575 WITH 425 SX CMT
SURF Size: 8.625 feet: 1604 WITH 625 SX CMT

\$181¹⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2004 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: WAYNE WILSON Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: PUMP 400# HULLS & 30 SX CMT. PERFORATE AT 1600' & CIRCULATE TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2004 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5514'. PUMP 300# HULLS WITH 30 SX CMT. PRESSURED TO 2000 PSIG & SHUT IN. CMT TO 550'. RIG UP TO BACKSIDE & PUMP 5 BBL WATER AHEAD. NO PRESSURE. START PUMPING CMT. PRESSURED TO 850 PSIG. PUMP CMT AWAY AT 400 PSIG. PUMPED 5 BBL OVER 4 1/2" X 8 5/8" ANNULUS CASING CAPACITY OF 70 BBL. SHUT IN PRESSURE 400 PSIG. TOTAL IN 4 1/2" X 8 5/8" ANNULUS 275 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5490	5494		

RECEIVED
MAR 04 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
MAR - 1 2004
KCC Dodge City

Signed

Jim Holland **PERT II**
INVOICE
(TECHNICIAN)

DATE: 3-4-04
NO. NO: 2004061251

Form C-27
[Signature]