

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20194-00-01
Spot: NENENE Sec/Twnshp/Rge: 36-17S-41W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: SMITH CATTLE Well #: 4
County: GREELEY Total Vertical Depth: 3120 feet

Operator License No.: 6085
Op Name: SMITH RANCH COMPANY
Address: HC 2 BOX 201
SHARON SPRINGS, KS 67758

PROD Size: 4.5 feet: 3118 WITH 550 SX CMT
SURF Size: 8.625 feet: 255 WITH 250 SX CMT

10140

Well Type: SWD UIC Docket No: D20433.0 Date/Time to Plug: 02/23/2004 9:00 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: DAVE OLSON Company: SMITH RANCH CO. Phone: (785) 852-4653

Proposed Plugging Method: PUMP 300# HULLS & 140 SX CMT. PRESSURE CHECK. CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2004 9:30 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 3118'. PUMPED DOWN 4 1/2" CASING 300# HULLS & 140 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN PRESSURE 500#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 15 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 500#.

Perfs:

Top	Bot	Thru	Comments
1912	1954		

RECEIVED
MAR 04 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
MAR - 3 2004
KCC Dodge City

Signed

Kevin D. Strube

(TECHNICIAN)

INVOICED

DATE

3-4-04

WV. NO.

2004061260

Form CE 2/03

[Signature]