

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20797-00-00
Spot: NWSESESW Sec/Twnshp/Rge: 12-11S-18W
111 feet from S Section Line, 2701 feet from E Section Line
Lease Name: BEMIS CO-OP STR INJ Well #: W-04
County: ELLIS Total Vertical Depth: 3220 feet

Operator License No.: 32754
Op Name: ELYSIUM ENERGY, L.L.C.
Address: 1625 BROADWAY, SU 2000
DENVER, CO 80202

PROD Size: 5.5 feet: 3214 w/175 sxs cmt
SURF Size: 8.625 feet: 1112 w/450 sxs cmt

#10465

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 02/02/2004 1:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DAVE STAHL Company: ELYSIUM ENERGY, L.L.C. Phone: (785) 434-4638

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls - 13 sxs gel spacer.
Fluid level 2200'. PBSD 2957'.
Note: Footages from south and east are correct as indicated.
Configured as injector, but never used as such.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/26/2004 1:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2945'.
Allied pumped 13 sxs gel spacer with 200# hulls, followed with 50 sxs 60/40 pozmix - 10% gel with 200# hulls.
Pulled tubing to 1114'.
Allied pumped 100 sxs cwc.
PTOH. Squeezed with 15 sxs cement. S.I.P. 500#.
Hooked up to 8 5/8" and pumped 1/2 bbl. Leak around 8 5/8" braden head.
02-26-2004 - Welder orange peeled 8 5/8" to 5 1/2" casing.
Allied pressured up to 500# instant.

Perfs:

Top	Bot	Thru	Comments
2952	3159		

RECEIVED
MAR 04 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

INVOICED

DATE 3-4-04
INV. NO. 2004061254

Form CP-2/3

FEB 27 2004

PHILLIPS PETROLEUM CO. #W-04 BEMIS CO-OP 12-11-18W
 GREAT BEND, KANSAS WTR. INJ. 50'NW SE SE SW
 CONTR GARVEY DRILLING CTY ELLIS

GEOL FIELD BEMIS-SHUTTS

E 1860 KB CM 2/1/72 CARD ISSUED 4/27/72 IP WIW/TOP 2952-78 & LANS 3088-3159

API 15-051-20,797

SMP	TOPS	DEPTH	DATUM
TOP		2814	= 954
HEEB		3013	=1153
TOR		3032	=1172
LANS		3056	=1196
ARB NOT REACHED			
RTD		3220	=1360

8 5/8" 1112/450sx; 5 1/2" 3214/175sx
 NO DSTS
 MICT, PF 8/2952-56, 8/2960-64, 16/2970-78(TOP), 20/3088-98, 16/3151-59(LKC), 2500 ACID,
 NO LOG

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

MAGNET

DATE