

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20040-00-00  
Spot: NWSE Sec/Twnshp/Rge: 5-22S-33W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: GARDEN CITY B Well #: 5  
County: FINNEY Total Vertical Depth: 4790 feet

Operator License No.: 30535  
Op Name: HARTMAN OIL CO., INC.  
Address: 12950 E. 13TH  
WICHITA, KS 67230

CIBP Size: feet: 1150  
PROD Size: 5.5 feet: 4789 WITH 225 SX CMT  
SURF Size: 8.625 feet: 427 WITH 325 SX CMT

*A 155-68*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/01/2004 1:30 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: STAN MITCHELL Company: HARTMAN OIL Phone: (620) 277-2511

Proposed Plugging Method: AS PER KCC-(KEVIN STRUBE)- SET CMT RETAINER @ 3700', SQUEEZE OF PERFORATIONS WITH 100 SX CLASS A CMT. TEST CSG TO 500#, PERFORATE CSG @ 1100' CIRCULATE CMT TO SURFACE, CAP OFF.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/02/2004 11:30 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4762'. RUN TUBING IN HOLE WITH CEMENT RETAINER SET @ 3700'. COULD NOT PUMP INTO. PRESSURED UP TO 1000#. PULLED OUT & SPOTTED 10 SX CMT ON TOP. PRESSURE TEST CASING. PUMPED INTO @ 2 3/4 BPM @ 500#. 3/2/04: SET CIBP @ 1150'. PRESSURE TESTED CASING TO 500#. PERFORATED AT 1100#. PUMPED DOWN 5 1/2" 175 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN PRESSURE 300#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 70 SX CMT. MAXIMUM PRESSURE 600#. SHUT IN PRESSURE 250#.

Perfs:

Top	Bot	Thru	Comments
4716	4728		
4628	4634		
4376	4388		
4318	4322		

RECEIVED  
MAR 04 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

RECEIVED  
MAR - 3 2004  
KCC Dodge City

Signed \_\_\_\_\_

*Kevin D. Plate*  
(TECHNICIAN)

INVOICED  
DATE 3-4-04  
INV. NO. 2004061255

Form 223  
*[Signature]*