

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-10364-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 6-21S-11W  
986 feet from S Section Line, 1768 feet from E Section Line  
Lease Name: DIETZ Well #: 5  
County: STAFFORD Total Vertical Depth: 3480 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

PROD Size: 5.5 feet: 3479 WITH 150 SX CMT  
SURF Size: 8.625 feet: 260 WITH 165 SX CMT

*\$113<sup>10</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/02/2004 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: RUN TUBING TO 1420'. PUMPED 10 SX GEL & 25 SX CMT WITH 100# HULLS. PERFORATED AND CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/02/2004 1:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3472'. 2 3/8" TUBING STUCK @ 1450'. BACK OFF TUBING @ 1420'. RAN TUBING TO 1420'. PUMPED 10 SX GEL & 25 SX CMT WITH 100# HULLS. PERFORATED 5 1/2" @ 600'. PULLED TUBING TO 600'. PUMPED 250 SX CMT DOWN TUBING CIRCULATING CMT TO SURFACE UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS. PULLED TUBING. TOPPED OFF 5 1/2" & 8 5/8" X 5 1/2" ANNULUS WITH 30 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3466	3470		
3458	3462		
3442	3450		

RECEIVED  
MAR 04 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

*Richard W. Lacey*

(TECHNICIAN)

INVOICED

DATE

3-4-04

NO. INCL

2004061256

Form