

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-01729-00-00
Spot: SESWSE Sec/Twnshp/Rge: 25-21S-13W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: FISCHER B Well #: 10
County: STAFFORD Total Vertical Depth: 3675 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN, LLC
Address: 3200 FIRST PLACE TOWER
TULSA, OK 74103

PROD Size: 7 feet: 3502 WITH 100 SX CMT
SURF Size: 10.75 feet: 325 WITH 275 SX CMT

119 44

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOHN "ART" ROLO Company: _____ Phone: (785) 737-3530

Proposed Plugging Method: TUBING TO 3300'. PUMP 20 SX GEL - 50 SX CMT - 100# HULLS. PERFORATE AT 730'. CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/26/2004 12:58 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3416'. ANHYDRITE @ 730'. RAN TUBING TO 3300'. PUMPED 20 SX GEL FOLLOWED BY 50 SX CMT WITH 100# HULLS. PERFORATED 7" AT 730'. PULLED TUBING TO 730'. PUMPED 235 SX CMT. CIRCULATED CMT TO SURFACE UP 7" CASING & 10 3/4" X 7" ANNULUS. PULLED TUBING OUT OF HOLE. FILLED 7" & 10 3/4" BACK TO SURFACE WITH 70 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3382	3386		CMT PLUG @ 3416'

RECEIVED
MAR 04 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District:



Signed

Richard M. Lacey

(TECHNICIAN)

INVOICED
DATE 3-4-04
INV. NO. 2004061257

Form 10-2/03
[Signature]