

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-147-19039-00-00  
 API NUMBER \_\_\_\_\_

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE NAME Schluntz  
 WELL NUMBER 6

\_\_\_\_\_ Ft. from S Section Line  
 \_\_\_\_\_ Ft. from E Section Line

LEASE OPERATOR Graham-Michaelis Corporation  
 ADDRESS P.O. Box 232 Russell, KS. 67665  
 PHONE#(913) 483-3136 OPERATORS LICENSE NO. 5134

SEC. 19 TWP. 1S RGE. 18W \*E) or (W)  
 COUNTY Phillips

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed \_\_\_\_\_  
 Plugging Commenced 9-19-90  
 Plugging Completed 10-4-90

The plugging proposal was approved on \_\_\_\_\_ (date)  
 by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3590'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	225'	none
				5 1/2"	3589'	1066'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Sanded bottom to 3310', ran 4 sacks cement. Shot pipe @1800', 1500', 1300', 1200', 1066'. Pumped down 8 5/8" 260 sacks cement w/500# hulls. Max pressure 900# Closed w/500# holding.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050  
 Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graham-Michaelis Corporaiton

STATE OF Kansas COUNTY OF Rice, ss. OCT 19 1990


R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 18 day of Oct., 19 90

My Commission Expires:



*Irene Herzberg*  
 Notary Public

15-147-19039-00-00

DRILLER'S LOG

COMPANY:	FELDT-MAYTAG & COMPANY
CONTRACTOR:	LEBEN DRILLING, INC.
FARM:	SCHLUNTZ #6
LOCATION:	C SE SE SEC. 19-1-18W PHILLIPS COUNTY, KANSAS
COMMENCED:	3-4-60
COMPLETED:	3-12-60

0	85	Surface Clay & Shale
85	227	Shale
227	735	Shale
735	1250	Shale & Sand
1250	1480	Shale
1480	1724	Shale & Shells
1724	1730	Anhydrite
1730	1975	Shale & Shells
1975	2275	Shale & Lime
2275	2345	Shale & Lime
2345	2545	Shale & Shells
2545	2665	Shale
2665	2785	Shale & Lime
2785	3005	Shale & Lime
3005	3195	Shale & Lime
3195	3325	Shale & Lime
3325	3365	Lime
3365	3415	Lime
3415	3550	Lime
3550	3590	Lime
	<u>3590</u>	<u>Rotary Total Depth</u>

Set 8 5/8" surface casing @ 225' with 170 sacks Sunset cement.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Schluntz #6, located C SE SE of Section 19, Township 1 South, Range 18 West, Phillips County, Kansas, as reflected by the files of Leben Drilling, Inc.

*Frank Hamlin*  
 \_\_\_\_\_  
 Frank Hamlin

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 17th day of March, 1960.

*Juanita M. Green*  
 \_\_\_\_\_  
 Juanita M. Green, Notary Public

RECEIVED  
 JUL - 6 1990  
 CONSERVATION DIVISION  
 Wichita, Kansas

My Commission Expires:  
April 23, 1963

RECEIVED  
 MAR 21 1960  
 C. L. F. □  
 J. H. M. □