

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-147-19040-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Phillips County. Sec. 19 Twp. 1 Rge. 18 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____

Lease Owner C SW/4 SE/4
Lease Name Sierra Petroleum Co., Inc. Well No. _____
Schlumtz #7
Office Address Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8/7/80 19____
Plugging completed 8/12/80 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, depleted
date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3620
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					no record	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Fluid at 370', hole filled with BS at 1000'. Shot pipe off at 810
and pulled 25 joints. Pumped 3 sacks hulls, 8 sacks gel, 70 sacks
cement, 10 sacks gel, 2 sacks hulls and 70 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of August, 19 80

My commission expires _____



15-147-19040-00-00

DRILLER'S LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:

FELDT-MAYTAG & COMPANY
LEBEN DRILLING, INC.
SCHLUNTZ #7
C SW SE. SEC. 19-1S-18W
PHILLIPS COUNTY, KANSAS
9-22-60
9-29-60

COMMENCED:
COMPLETED:

0	60	Shale & Sand
80	223	Shale
223	700	Shale & Shells
700	1455	Shale
1455	1775	Shale
1775	1835	Shale & Shells
1835	1845	Anhydrite
1845	1885	Shale & Shells
1885	2300	Shale
2300	2450	Shale & Lime
2450	2675	Shale & Shells
2675	2875	Lime
2875	3165	Shale & Lime
3165	3355	Shale & Lime
3355	3420	Lime
3420	3472	Lime
3472	3620	Lime
	<u>3620</u>	<u>Rotary Total Depth</u>

Set 8 5/8" surface casing @ 218' with 150 sacks Quick Set by Halliburton

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Schluntz #7, located C SW SE of Section 19, Township 1 South, Range 18 West, Phillips County, Kansas, as reflected by the files of Leben Drilling, Inc.

Frank Hamlin
Frank Hamlin

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 5th day of October, 1960.

Bette J. Behymer
Bette J. Behymer, Notary Public

My Commission Expires:
July 27, 1964

RECEIVED
STATE CORPORATION COMMISSION
JUL 10 1980
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
OCT 14 1960
C. L. F. □
A. B. M. □