

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-147-14041-00-00
 API NUMBER _____

LEASE NAME Schluntz

WELL NUMBER 8

_____ Ft. from S Section Line

_____ Ft. from E Section Line

SEC. 19 TWP. 1S RGE. 18W (E) or (W)

COUNTY Phillips

Date Well Completed _____

Plugging Commenced 9-24-90

Plugging Completed 10-4-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Graham-Michaelis Corporaion

ADDRESS P.O. Box 232 Russell, KS. 67665

PHONE#(913) 483-3136 OPERATORS LICENSE NO. 5134

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3620'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	217'	none
				4 1/2"	3619'	1141'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Sanded bottom to 3370', ran 4 sacks cement. Shot pipe @1600', 1400', 1200', 1141'. Pumped down 8 5/8" 425 sacks 65/35 poz and 700# hulls. Max pressure 300# Closed w/100 lbs. holding.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graham-Michaelis Corporation

STATE OF Kansas COUNTY OF Rice, ss. 10-19-90

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 18 day of Oct., 19 90

[Signature]
 Notary Public

My Commission Expires _____



DRILLER'S LOG 15-147-19041-00-00

COMPANY: FELDT-MAYTAG & COMPANY
CONTRACTOR: LEBEN DRILLING, INC.
FARM: SCHLUNTZ #8
LOCATION: C NE SE SEC. 19-18-18W
PHILLIPS COUNTY, KANSAS
COMMENCED: 9-30-60
COMPLETED: 10-7-60

0	85	Surface Soil & Shale
85	217	Shale
217	800	Shale
800	1540	Shale, Sand & Shells
1540	1790	Shale
1790	1820	Anhydrite
1820	1945	Shale w/ Lime
1945	2325	Shale & Chalk
2325	2545	Shale & Lime
2545	2845	Shale & Lime
2845	3078	Shale & Lime
3078	3230	Shale & Lime
3230	3445	Lime
3445	3530	Lime
3530	3590	Lime
3590	3620	Lime
	<u>3620</u>	<u>Rotary Total Depth</u>

Set 8 5/8" surface casing @ 217' with 150 sacks of Quick Set.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Schluntz #8, located C NE SE of Section 19, Township 1 South, Range 18 West, Phillips County, Kansas, as reflected by the files of Leben Drilling, Inc.

Frank Hamlin
Frank Hamlin

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 12th day of October, 1960.

Bette J. Behymer
Bette J. Behymer, Notary Public

My Commission Expires:
July 27, 1964

RECEIVED
JUL - 6 1960
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
OCT 20 1960
C. L. F. [initials]
I. B. M. [initials]