

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-147-19042-00-00  
APT NUMBER 10-9-1960

LEASE NAME Schluntz

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #9

           Ft. from S Section Line

           Ft. from E Section Line  
C NW SE

SEC. 19 TWP. 1S RGE. 18 (~~E~~W)

COUNTY           

LEASE OPERATOR Graham-Michaelis Corporation

ADDRESS P. O. Box 247, Wichita, KS 67201

PHONE#(316) 264-8394 OPERATORS LICENSE NO. 5134

Date Well Completed 10-19-60

Character of Well Oil

Plugging Commenced 8-26-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-26-88

The plugging proposal was approved on August 15, 1988 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?           

Producing Formation Lansing-Kansas City Depth to Top 3391' Bottom 3510' T.D. 3580

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	215'	none
				4 1/2"	3579'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Ran 80 joints of tubing to 2520'. Spotted 50 sacks 60/40 poz mix 8% gel. Pulled 35 joints tubing. Spotted 50 sacks cement. Pulled out with tubing. Pumped 10 sacks cement with 1 sack hulls down casing. Casing pressured to 750# and it held. Pumped 145 sacks cement with 400# hulls down backside. Pressured to 700# and it held.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Graham-Michaelis Corporation License No. 5134

Address P. O. Box 247, Wichita, KS 67201


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graham-Michaelis Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Norman Rodie (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) D.R. Clark

(Address) Box 232, Russell, KS 67665



AND SWORN TO before me this 22nd day of September, 19 88

6-19-91

Viola M. Thowe  
Notary Public

My Commission Expires: June 19, 1991