

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-20004-00-001

API NUMBER _____

LEASE NAME Schluntz

WELL NUMBER 9

SPOT LOCATION C E/2 SW

SEC. 20 TWP. 1S RGE. 18 XXXX(W)

COUNTY Phillips

Date Well Completed 7-67

Plugging Commenced 8-19-85

Plugging Completed 8-19-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ladd Petroleum Corporation

ADDRESS Box 520, Great Bend, Kansas 67530

PHONE #(316) 792-3571 OPERATORS LICENSE NO. 6029

Character of Well Input
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas District #6

Is ACO-1 filed? _____ if not, is well log attached? _____

Producing formation LKC Depth to top 3410 bottom 3459 T.D. 3800

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	230'	None
LKC	Oil & Water	3410	3459	4 1/2	3800	None

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Down 4 1/2 csg mixed 25 sx 60/40 poz w/5 sx hulls- 10 sx gel w/5 hulls, release plug, mixed 100 sx 60/40 poz w/5 sx hulls, SI Press. 700#
Between 4 1/2 & 8 5/8 csg mixed 75 sx 60/40 poz w/5 sx hulls, 15 sx gel w/5 sx hulls, 100 sx 60/40 poz, SIP 200#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. _____
Address Great Bend, Kansas 67530

STATE OF _____ COUNTY OF _____, ss.

Jerry Rice (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Rice
(Address) Box 520, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 3 day of September, 1985

Ramona L. Dunlap
NOTARY PUBLIC
State of Kansas
EXPIRES 7-23-88

RECEIVED
STATE CORPORATION COMMISSION
Ramona L. Dunlap
Notary Public
SEP 4 1985

My Commission expires: _____

DRILLER LOG 15-147-20004-00-~~2801~~

Schluntz No. 9

CASING RECORD:
8 5/8" @ 231'
w/150 sx cement
4 1/2" @ 3610'
w/150 sx cement

COMPANY: Livingston Oil Co.
CONTRACTOR: Red Tiger Drilling Co.
COMMENCED: July 9, 1967
COMPLETED: July 14, 1967

DESCRIPTION:
1800' E of WL &
1200' N of SL
20-1S-18W
Phillips County,
Kansas

ELEVATION:

TOTAL DEPTH: 3800'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	0	60	
Sand & Shale	60	235	
Shale, Sand & Shale	235	1290	
Shale	1290	1801	
Anhydrite	1801	1821	
Shale	1821	2375	
Lime & shale	2375	3465	
Lime	3465	3698	
Lime & shale	3698	3795	
Lime	3795	3800	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Starr
Maxine V. Starr

Subscribed and sworn to before me this 17th day of July, 1967.

Retty M. Maloney
Notary Public

My Commission Expires:
3-22-71

RECEIVED
STATE CORPORATION COMMISSION

JUN 06 1985

CONSERVATION DIVISION
Wichita, Kansas