

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 9-13-51

15-147-00879-00-01

LEASE NAME Stevens

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 3

SPOT LOCATION SW NE SE

SEC. 21 TWP. 1S RGE. 18 XXXXX (W)

COUNTY Phillips

LEASE OPERATOR Ladd Petroleum Corporation

Date Well Completed 9-13-51

ADDRESS Box 520, Great Bend, Kansas 67530

Plugging Commenced 8-19-85

PHONE # (316) 792-3571 OPERATORS LICENSE NO. 6029

Plugging Completed 8-19-85

Character of Well Input
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation LKC Depth to top 3435 bottom 3489 T.D. 3494

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4	202'	None
LKC	Oil & Water	3434	3489	5 1/2	3531	None

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Down 5 1/2' csg mixed 40 sx 60/40 poz w/5 sx hulls, 15 sx gel mud, w/5 sx hulls, 110 sx 60/40 poz w/5 sx hulls, SI Press 600#
Between 5 1/2' & 10 3/4' csg mixed 50 sx 60/40 poz w/5 sx hulls, 10 sx gel mud w/5 sx hulls, 100 sx cement 60/40 poz, SI Press. 200#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. _____
 Address Great Bend, Kansas 67530

STATE OF _____ COUNTY OF _____, ss.

Jerry Rice (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Rice
 (Address) Box 520, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 3 day of September, 1985

My Commission expires: _____

Ramona L. Dunlap
 NOTARY PUBLIC
 State of Kansas
 MY APPT. EXPIRES 1-23-88

RECEIVED
 STATE CORPORATION COMMISSION

SEP 4 1985

Office Memorandum

From Kent Kimball

Date October 12, 1951

To Forrest H. Lindsay

Subject #3 E. L. Stevens

SW NE SE of 21-1S-18W
Phillips County, Kansas

Type: Huffstutter Pool well

Elev.: 2193'GR
2195'DF

Status: Oil Well

15-147-00879-00-01

Dates: Spudded September 2, 1951; under surface September 4, 1951; long string run September 14, 1951.

Casing: Ran 202' of 8-5/8" set at 202' w/125 sx; ran 3528' of 5-1/2" set at 3528' w/150 sx.

Special tests: Johnston Testers; Schlumberger

TOPS

<u>Formation</u>	<u>Sample</u>	<u>Schlumberger</u>	<u>Readings</u>
Topeka		3097	
Heebner Shale	3352	3355	
Lans.-K.C.	3380	3380	
Oil Zones:			
1st	3430-40	3429-40	42/37/16
2nd		3450-60	9/34/21
3rd		3475-84	10/37/15
Total Depth:	3531'(Driller)	3532'	

DESCRIPTIONS OF SPECIAL TESTS

DST #1 - 3390-3438; Open 1 hour; weak blow 45 min.; Rec. 30' OCM, 30' O & GCM, 30' HOCCM; BHP 940#

DST #2 - 3439-83; Open 1 hour; weak blow 13 min.; Rec. 20' OCM; BHP zero.

Respectfully submitted;

Kent Kimball
by C. H.

KK:cg

RECEIVED
STATE CORPORATION COMMISSION

JUN 06 1985

CONSERVATION DIVISION
Wichita, Kansas