

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-21423-00-00

LEASE NAME Miller M

WELL NUMBER 2

1250 Ft. from S Section Line

4030 Ft. from E Section Line

SEC. 20TWP. 34RGE. 40 or (W)

COUNTY Morton

Date Well Completed 2-22-96

Plugging Commenced 2-3-04

Plugging Completed 2-3-04

RECEIVED

MAR 03 2004

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, KS 67905

PHONE(S) (620) 629-4860 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-2-04 11-4-03 (date)

by Jim Holland (KCC District Agent's Name)

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation Chase Depth to Top 2476 Bottom 2564 T.O. 2765

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>			<u>516</u>	<u>8 5/8</u>	<u>516</u>	<u>-</u>
<u>Prod.</u>			<u>2719</u>	<u>5 1/2</u>	<u>2719</u>	<u>817</u>
<u>RBP</u>			<u>2047</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from ___ feet to ___ feet each s
RBP @ 2047 Shot 5 1/2 Attempt to circ. hole (no circ.) mixed 200 lb of 30sx cont.
from 817 to 717. Pull to 530 Circ. hole w/mud & mixed 50 sx 530 to 380
10 sx 40 to 0 Cut off & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Seward, ss.


Kenny Andrews (Employee of Operator) or (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well, as filed the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 1st day of March, 192004

Anita Peterson
Notary Public



Commission Expires: Oct. 1, 2005