

WELL PLUGGING RECORD

K.A.R.-82-3-117

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

TYPE OR PRINT  
NOTICE: Fill out Completely  
and return to coms. div.  
office within 30 days.

API NUMBER 15-053 20 615 - 00-00  
LEASE NAME Harbacek  
WELL NUMBER 1  
1650 ft. from S Section Line  
660 ft. from E Section Line  
SEC. 8 TWP. 16 RGE. 10 (E) or (W)

COUNTY Ellsworth  
Date Well Completed 3-16-1981  
Plugging Commenced 2/29/04  
Plugging Completed 2/23/04

LEASE OPERATOR Younger Energy company  
ADDRESS 453 S. Webb Road, Suite 100, Wichita, KS 67207  
PHONE # (316) 681-2542 OPERATORS LICENSE NO. 30705

Character of well oil  
(Oil, Gas, D&A, SWD, input, Water Supply Well)

The plugging proposal was approved on 2/20/04  
by Doug Louis KCC WICHITA (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached not available to us

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3315  
Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Sand			277	8 5/8	277	none
Prod			3314	4 1/2	3314	1430

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set

Sand at 3201, bail 4 sacks cem, Rip pipe at 1624, 1430, work free. Pull to 1000, pump 35 sacks cem and 2 sacks hulls. Pull to 650, pump 35 sacks cem and 2 hulls. Pulled to 325, circulate cement to surface with 60 sacks cement. Pull rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925  
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Younger Energy Company

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


DIANE REBSTOCK (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) Diane Rebstock, V.P. Younger  
(Address) 453 S. Webb, #100, Wichita, KS 67207

SUBSCRIBED AND SWORN TO before me 2nd day of March, 2004

Notary Public

My commission Expires:



Form CP-4 Revised 05-88