

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-065-21833-00-00

LEASE NAME Hoeting Unit

TYPE OR PRINT

WELL NUMBER #2-10

NOTICE: Fill out **completely** 2310' Ft. from S Section Line  
and return to Cons. Div. 1650' Ft. from E Section Line  
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 29 TWP9S RGE. 24W (E) or (W)  
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY Graham  
PHONE # (316 ) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 8/21/83  
Character of Well O (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 1/21/04  
Plugging Completed 1/21/04

The plugging proposal was approved on 1/21/04 (date)

by Pat Staab w/KCC (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? \_\_\_\_\_

Producing Formation LKC Depth to Top 4074' Bottom 4100' TD4175' Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	249'	8 5/8	249'	0
		Production	4170'	4 1/2	4170'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged well as follows:

RIH w/2 3/8" tbg to 2356'. RU Swift Services. Tied onto 8 5/8". Pumped 5 sacks SMD. Pressured to 350# & held. Tied onto 2 3/8" tbg. Pumped 100 sacks SMD, 500# hulls to circ cmt to surface. TOH w/ 23/8" tbg. Tied onto 4 1/2" csg. Pumped 50 sacks SMD. Max pressure 500#, ISIP 400#. Plugged @2:30 PM. Witnessed by Pat Staab w/KCC. RDMO #425

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606  
Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) Wichita, KS


SUBSCRIBED AND SWORN TO before me this 6th day of February, 2004

Notary Public - Kristin Grady  
My Commission Expires: 2/06/08



Form CP-4 Revised 05-88

RECEIVED  
MAR 03 2004  
KCC WICHITA



CHARGE TO: *Mufin Drig. Co.*  
 ADDRESS:  
 CITY, STATE, ZIP CODE: *Hill City, Ks*

RECEIVED  
 MAR 03 2004  
 KCC WICHITA

TICKET No 6252

PAGE 1 OF 1

SERVICE LOCATIONS 1. <i>Hayok</i>	WELL/PROJECT NO. <i>2-10</i>	LEASE <i>Hoeting</i>	COUNTY/PARISH <i>Irahan</i>	STATE <i>KS</i>	CITY	DATE <i>1-21-04</i>	OWNER <i>Same</i>
2.	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR	RIG NAME/NO. <i>Mufin</i>	SHIPPED VIA <i>105</i>	DELIVERED TO <i>S.W. Hill City</i>	ORDER NO.	
3.	WELL TYPE <i>oil</i>	WELL CATEGORY <i>abandoned</i>	JOB PURPOSE <i>P.T.A.</i>	WELL PERMIT NO.	WELL LOCATION		
4. REFERRAL LOCATION	INVOICE INSTRUCTIONS						

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
<i>575</i>					MILEAGE <i>105</i>	<i>50</i>		<i>mi</i>		<i>2.50</i>	<i>125.00</i>
<i>576</i>					<i>Pump charge</i>	<i>1</i>		<i>GA</i>			<i>550.00</i>
<i>275</i>					<i>Hulls</i>	<i>7</i>		<i>SKS</i>		<i>20.00</i>	<i>140.00</i>
<i>330</i>					<i>smo Cement</i>	<i>155</i>		<i>SKS</i>		<i>9.75</i>	<i>1511.25</i>
<i>581</i>					<i>Bulk Service charge</i>	<i>200</i>					<i>200.00</i>
<i>583</i>					<i>Drayage</i>	<i>498</i>			<i>T.M.</i>	<i>85</i>	<i>423.30</i>

**LEGAL TERMS:** Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X.  
 DATE SIGNED *1-21-04* TIME SIGNED *1:00*  A.M.  P.M.

REMIT PAYMENT TO:

SWIFT SERVICES, INC.  
 P.O. BOX 466  
 NESS CITY, KS 67560  
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	<i>2949.55</i>
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?					
WE UNDERSTOOD AND MET YOUR NEEDS?					
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	<i>156.33</i>
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	<i>3105.88</i>
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR *Lenny* APPROVAL *John Gust*

Thank You!

**JOB LOG**

**SWIFT Services, Inc.**

DATE 1-21-04 PAGE NO. 1

CUSTOMER Murphy Dole Co. WELL NO. 2-10 LEASE Hoeting JOB TYPE P.T.A. TICKET NO. 6252

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1245							on loc 4 1/2 T.D. 4100
5			2.7 BB <sup>l</sup>					open end Tbg at 2356 Hook up to 8 5/8 Pump 5 SKS CMT PSI To 350 + held well had been 2 staged
00			58 BB <sup>l</sup>					Hook up to Tbg + Pump 100 SKS SMD CMT + 500# Hulls CMT circ to Pit
	1330							Pull Tbg out of hole
50							500	Hook up to 4 1/2 CSG + Pump 50 SKS
							500	Cement 500 max PSI
							400	shut in 5 1/2 w/ 400 PSI
	1530							Job Complete
								5 1/2 150 SKS CMT 500# hulls max PSI 500 Shut in 400 PSI
								8 5/8 5 SKS CMT max PSI 350

RECEIVED

MAR 03 2004

KCG WICHITA