

RECEIVED

FEB 02 2004

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

KCC WICHITA

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

15-073-19348-00-00  
API # 2-7-57 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Schankie Well Service, Inc. KCC LICENSE # 6470  
(owner/company name) (operator's)

ADDRESS 1006 SW Blvd, P O Box 397 CITY Madison

STATE Kansas ZIP CODE 66860 CONTACT PHONE # (620) 437-2595

LEASE Derbyshire WELL# 8 SEC. 13 T. 22S R. 10 (East/West)

NW-NE - NE - SE SPOT LOCATION/QQQQ COUNTY Greenwood

~~2590~~ 2590 FEET (in exact footage) FROM SN (circle one) LINE OF SECTION (NOT Lease Line)

~~610~~ 610 FEET (in exact footage) FROM EW (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL X GAS WELL      D&A      SWD/ENHR WELL      DOCKET#     

CONDUCTOR CASING SIZE NA SET AT      CEMENTED WITH      SACKS

SURFACE CASING SIZE 12 1/2" SET AT 103' CEMENTED WITH NA SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 2094' CEMENTED WITH 75 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Open Hole 2094'-2124'

ELEVATION NA T.D. 2124' PBTD 2115' ANHYDRITE DEPTH NA  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR      CASING LEAK      JUNK IN HOLE     

PROPOSED METHOD OF PLUGGING Plug back bottom to 2040' w/sand and 5sx cement

cap, shoot pipe off @ 850', pump 25sx cement plug, pump gel spacer to

150', shoot pipe off @ 150', pump 100sx cement plug to surface

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? no

If not explain why? Well drilled in 1957.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Clifford Schankie PHONE# (620) 437-2595

ADDRESS P O Box 397 City/State Madison, Kansas 66860

PLUGGING CONTRACTOR Schankie Well Service, Inc. KCC LICENSE # 6470  
(company name) (contractor's)

ADDRESS P O Box 397 Madison, KS 66860 PHONE # (620) 437-2595

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 11-17-03 Plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11-14-03 AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)

DRILLED FOR: L. B. Campbell et al,  
ADDRESS: MADISON, KANSAS

CONTRACTOR: Sauder Drilling Co.  
ADDRESS: Gridley, Kansas.

LEASE NAME: Derbyshire WELL #8

COMMENCED: January 25, 1957  
COMPLETED: February 7, 1957

ELEVATION:  
TOTAL DEPTH: 2124'

LOCATION: NE NE SE (610' W of E L & 2590' N  
of S L) Section 13-22-10e; Green-  
wood County, Kansas.

CASING RECORD:	run	pulled	size
	103' left in		12 1/2"
	644'	644'	10
	1277'	1277'	8
	2094'	Cemented W/75 Sx.	4 1/2

PRODUCTION: Est. 25 Bbls.

TREATMENT: Sand Frac'd W/25,000# sand

0 to 5' Soil  
45 Shale  
95 Sand (7-BW)  
103 Shale  
108 Lime  
125 Shale  
140 Lime  
195 Shale  
210 Lime  
255 Shale  
260 Lime  
370 Shale  
375 Lime  
405 Shale  
410 Lime  
415 Shale  
430 Lime  
500 Shale  
540 Lime  
595 Shale  
605 Lime  
610 Shale  
618 Lime  
625 Sand  
630 Shale  
640 Lime  
660 Shale  
680 Lime  
710 Shale  
720 Lime  
770 Shale  
780 Lime  
800 Shale  
825 Lime  
840 Shale  
860 Lime  
910 Shale  
915 Sand  
1070 Shale  
1075 Lime  
1105 Shale  
1115 Sand (2-BW)  
1155 Shale  
1270 Lime  
1385 Shale  
1565 Lime (1-BW @1430)  
1680 Shale  
1690 Lime  
1705 Shale

1725 Lime  
1790 Shale  
1800 Lime  
1822 Shale  
1830 Lime  
1840 Shale  
1845 Lime  
1930 Shale  
1940 Lime  
1950 Shale  
1955 Lime  
2091 Shale  
2123 Sand  
2124 Shale  
2124 Total Depth.

This log issued and filed with  
State Geological Society on  
February 16th, 1957.

11-14-03  
11-20-03