

REVISED

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

15-083-1035000-01

API # 15-083-10,350,0001 (Identifier Number of this well) This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 4/63

Well Operator: HARTMAN OIL CO., INC. (Owner / Company Name) KCC License #: 30535 (Operator's)

Address: 12950 E. 13TH ST. City: WICHITA

State: KANSAS Zip Code: 67230 Contact Phone: (316) 636 - 2090

Lease: BILLINGS Well #: 2 Sec. 36 Twp. 22 S. R. 23 East West

NW - NW Spot Location / QQQQ County: HODGEMAN

4545 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

4620 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: N/A Set at: N/A Cemented with: N/A Sacks

Surface Casing Size: 8 5/8" Set at: 246' Cemented with: 200 Sacks

Production Casing Size: 5 1/2" Set at: 4495' Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4495-4500' OPEN HOLE - (CIBP @4482') - PERFS @ 4386-92'

Elevation: 2260' (G.L. / K.B.) T.D.: 4500' PBDT: 4482' Anhydrite Depth: 1450'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): AS PER KCC - SPOT 2 SXS CEMENT ON CIBP @ 4350'
RUN CEMENT BOND LOG FROM 1500' - TO SURFACE - (IF NO CEMENT) - PERFORATE 2 HOLES @ 600' - CIRCULATE
TO SURFACE W/200 SXS 60/40 POZ W/6% GEL - CUT CSG OFF - 4' BELOW GROUND LEVEL WELD & DATE CAP ON CSG W/PLUGGED DATE

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? DRILLED 4/63 (LOG SENT WITH PREVIOUS INCORRECT APPLICATION)

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: STAN MITCHELL

HARTMAN OIL CO., INC. Phone: (620) 277 - 2511

Address: 4550 W 9 MILE RD City / State: GARDEN CITY, KS. 67846

Plugging Contractor: PLAINS, INC. ~~ALLIED CEMENT~~ KCC License #: 4072 (Contractor's)

Address: P.O. BOX 346 - NESS CITY, KS 67560 Phone: (785) 798 - 3995

Proposed Date and Hour of Plugging (if known?): AS WEATHER PERMITS

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/15/04 Authorized Operator / Agent: Mary King (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

JAN 16 2004

KCC WICHITA

10/04

11/04

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Hartman Oil Co., Inc.
12950 E. 13th
Wichita, KS 67230

January 20, 2004

Re: BILLINGS #2
API 15-083-10350-00-01
NWNW 36-22S-23W, 4545 FSL 4620 FEL
HODGEMAN COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888