

RECEIVED
JAN 28 2004
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 081-20,501 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 8/16/88

Well Operator: BEREXCO INC. KCC License #: 5363
(Owner / Company Name) (Operator's)

Address: P.O. BOX 20380 City: WICHITA

State: KS Zip Code: 67208 Contact Phone: (316) 265 - 3311

Lease: MILLER TRUST Well #: 1-31 Sec. 31 Twp. 30 S. R. 33 East West
32

SE SW Spot Location / QQQQ County: HASKELL

660 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1980 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 1853' Cemented with: 700 Sacks

Production Casing Size: 4 1/2" Set at: 5118' Cemented with: 475 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4994'-96', 4954'-58', 4889'-93', 4881'-85'

Elevation: 2904' (G.L. / K.B.) T.D.: 5790' PBTD: 5064' Anhydrite Depth: 1830'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): According to the rules and regulations of the State of Kansas Corporation Commission.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? LOGS WERE PREVIOUSLY FILED WITH THE ACO-1.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: GREG KLAUS

Phone: (316) - 772-8650

Address: _____ City / State: SUBLETTE, KS

Plugging Contractor: MIKE'S TESTING & SALVAGE KCC License #: 31529
(Company Name) (Contractor's)

Address: P.O. BOX 467, CHASE, KS 67524 Phone: (620) 938-2943

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/22/04 Authorized Operator / Agent: Evan C. Mayhew Evan C. Mayhew
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

LEASE MILLER TRUST WELL NO. 1-31 RPT# 15-081-20,501
 LOCATION SESW SEC 31-30S-32W COUNTY HASKELL STATE KS
 OPERATOR AKCO FIELD _____
 ELEVATION: GR 2892 DF _____ KB 2904
 DATE DRILLED 8/30/08 ZERO MEASUREMENT KB

RECEIVED
 JAN 28 2004
 KCC WICHITA

PRODUCING FORMATION _____
 PUMP SIZE: _____ SET AT _____ FEET
 ROD DESIGN: TUBING: _____ JTS OF _____ TBG
 7/8" _____ WITH _____ 'M.A. SET @ _____
 3/4" _____
 1/8" _____

8 5/8" SURF CSG @ 1853
 W/ 575 LITE SX CEMENT
 125 COM

9/6-9/20/08) DO DV Run band by RTA-5064 DV-3304
 Pawnee 4954-5B 45AF Nat. 2.9 BPH 15% OIL
 500g 15% 2 RPM 300# ISA-VAC 5.9 BPH 50% OIL (FLOWING)
 ON SITE - 1200# Killed well 00 BALLS 2% KCL
 Put on pumps MR, SN, 158-298
 IP-47°/244°/15"

2/1/03 Dump 1000g 15% w/ 5-3000 drum annulus
 Avg 3°/54" after dump job

4/25-4/30/03 Perf Ft Scott 4994-96 + Marmaton 4881-85
 + 4889-93 45AF w/ cap gun
 Ft Scott 100g 20% 1 MWPH, no gas
 Marmaton 4881-93 - 1500g 15% 20 balls 3 RPM 60# ISA-VAC
 Surb 2.8 WPH, fair gas flow
 TOP - Marmaton only above pkr.
 Test 10 MCF/D 1/10 WPA

5/9/03 Shut well down.

TOC-3

⊙ DV 3304
 150 SX LITE 50 SX COM

TOC-3910

4881-85 > MARMATON
 4889-93

4954-5B PAWNEE
 4994-96 FT SCOTT

4 1/2" 10.5# CSG @ 5118
 W/ 275 SX OF CMT
 THICK SET

- DST#1 4472-4517 LSG G
2050' SW 1140/1180
- DST#2 4940-63 PAWNEE
525' GML 1502/1502
- DST#3 5650-5700 ST LOUIS
370' MW 1672/1562

RTA-5790
 LTA-5703

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Berexco, Inc.
PO Box 20380
Wichita, KS 67208

February 02, 2004

Re: MILLER TRUST #1-31
API 15-081-20501-00-00
SESW 31-30S-33W, 660 FSL 1980 FWL
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888