

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202 **RECEIVED**

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER ¹⁵⁻167-23,248-00-00

LEASE NAME Soukup

WELL NUMBER 1

1800 Ft. from S Section Line

1800 Ft. from E Section Line

SEC. 3 TWP. 15 SRGE. 13W (E) or (W)

COUNTY Russell

Date Well Completed 2/22/04

Plugging Commenced 8:15PM 2/22/04

Plugging Completed 11:30PM 2/22/04

MAR 05 2004

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR JOHN O. FARMER, INC.

ADDRESS P.O. Box 352 Russell, KS 67665

PHONE/(785) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/20/04 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.B. 3400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	225'	8 5/8"	225-47'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set:

1st Plug @ 3300'W/25sks 15sks In Rat Hole Circulated 1st Plug 15 Minutes W/50Vis Mud

2nd Plug @ 830'W/25sks Plugs displaced with mud.

3rd Plug @ 430'W/80sks Total 155sks 60/40Poz 6%Gel W/1#FS/sk By Allied Cementing

4th Plug @ 40'W/10sks Completed @ 11:30PM 2/22/04

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31548

Address P.O. Box 763 Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: JOHN O. FARMER, INC.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

John O. Farmer IV

~~(Employee of Operator)~~ (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) John O. Farmer IV

(Address) John O. Farmer IV, Vice-President
P.O. Box 352, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 4th day of March, 2004

My Commission Expires:

Margaret A. Schulte
Notary Public
Margaret A. Schulte



Form CP-1
Revised 03-88