

RECEIVED

MAR 11 2004

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

TYPE OR PRINT

LEASE NAME Edwards

WELL NUMBER #1

2970 Ft. from N Section Line

1650 Ft. from E Section Line

SEC. 22 TWP. 18S RGE. 26W XCOR (W)

COUNTY Ness

LEASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE# (785) 798-3641 OPERATORS LICENSE NO. 31627

Date Well Completed 11/59

Character of Well oil

Plugging Commenced 2/12/04

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/13/04

The plugging proposal was approved on 2/11/04 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACQ-1 filed? unknown If not, is well log attached? no logs received

Producing Formation Mississipian Depth to Top _____ Bottom _____ T.D. 4453 4450

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	<u>Prod</u>		<u>4449</u>	<u>5 1/2</u>	<u>4449</u>	<u>439</u>
	<u>Surf</u>		<u>302</u>	<u>8.625</u>	<u>302</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet. Ran tubing to 2350' & spot a 20 sk plug of 60-40 6% gel. 2/13/04 Spotted 35 sk plug @ 1300'. Waited 2 hrs & pressured up cement plug - it held. Per lech perforated @ 1100', Swift mixed 80 sks 60-40 & displaced cement to 600'. Shot 5 1/2" casing off @ 439'. Pulled casing up to 320'. Pumped 50 sks 60-40. pulled 5 1/2" from well & topped w/5 sks cement. Job complete.


Name of Plugging Contractor Whitetail Crude, Inc License No. 31627

Address P O Box 544, Ness City, KS 67560-0544

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President Whitetail Crude, Inc (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God.



(Signature) Mike J. Fritzler
MIKE J. FRITZLER, President
(Address) P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN TO before me this 8th day of March, 2004

Debra Kerr
Debra Kerr Notary Public

My Commission Expires: 4/20/05

USE ONLY ONE SIDE OF EACH FORM