

RECEIVED

MAR 11 2004

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME Schaben C

WELL NUMBER #1

660 Ft. from N Section Line

1980 Ft. from E Section Line

SEC. 19 TWP. 17S RGE. 24W XXX or (W)

COUNTY Ness

LEASE OPERATOR Grand Mesa Operating Company

ADDRESS 200 East First St, Wichita, KS 67202

PHONE#( 316 ) 265-3000 OPERATORS LICENSE NO. 9855

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 12/79

Plugging Commenced 1/31/04 2/3/04

Plugging Completed 2/3/04

The plugging proposal was approved on 1/30/04 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? \_\_\_\_\_

Producing Formation Mississipian Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4441

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Surf Prod</u>			<u>376</u>	<u>8.625</u>	<u>376</u>	<u>0</u>
			<u>4440</u>	<u>5.5</u>	<u>4440</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each so Sanded 5 1/2" casing off to 4280' & capped sand plug w/2 sks cement via dump bailer Log Tech perforated 5 1/2" @ 1050', mixed 80 sks w/200# hulls & displaced. Mixed 95 sks of 60-40 poz 6% gel, loaded casing & shut in. Mixed 50 sks & pumped down the 8 5/8" Shut in @ 500# pressure. Job complete.


Name of Plugging Contractor Whitetail Crude, Inc License No. 31627

Address P O Box 544, Ness City, KS 67560-0544

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Grand Mesa Operating Company

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President Whitetail Crude, Inc (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God.



(Signature) Mike J. Fritzler  
Mike J. Fritzler, President  
(Address) P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN TO before me this 9th day of March, 2004 AKK

Debra Kerr  
Debra Kerr Notary Public

My Commission Expires: 4/20/05

USE ONLY ONE SIDE OF EACH FORM