

RECEIVED

MAR 09 2004

KCC WICHITA

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Gore Oil Company
Address: P.O. Box 2757, Wichita, KS 67201-2757
Phone: (316) 263-3535 Operator License #: 5552
Type of Well: Oil Docket #:
The plugging proposal was approved on: 12-11-03 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Topeka Depth to Top: 2946' Bottom: 3188' T.D. 3440'
L-KC Depth to Top: 3189' Bottom: 3434' T.D. 3440'

API Number: 15 - 163-01,620-00-00
Lease Name: Rostocil C
Well Number: 7
Spot Location (QQQQ): NE - NE - NW -
4950 Feet from North / South Section Line
2970 Feet from East / West Section Line
Sec. 10 Twp. 9 S. R. 19 East West
County: Rooks
Date Well Completed: 7-3-62
Plugging Commenced: 12-10-03
Plugging Completed: 12-10-03

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows include Surface and Production formations with handwritten data.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Open end 2 3/8" tbg @ 3100'. Pump 150 sx SMD cmt & 200# hulls. 10 bbls to circ to pit. Pull tbg to 1550'. Pump 150 sx cmt w/400# hulls. Cmt circ to surface. Pull tbg out of hole. Hook up to 10 3/4" & try to pressure up, couldn't. Hook up to 7" & pump 125 sx cmt, max psi 200. Top off w/25 sx cmt. Job complete.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382
Address: P.O. Box 466, Ness City, KS 67560-0466

Name of Party Responsible for Plugging Fees: Gore Oil Company
State of Kansas County, Sedgwick, ss.

Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M Jack
(Address) Wichita, KS



SUBSCRIBED and SWORN TO before me this 5th day of March, 20 04
My Commission Expires: 3-20-07
Notary Public