

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202 RECEIVED

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-035-21064-00-00

API NUMBER 15-035-21064

LEASE NAME Gatton

WELL NUMBER 1#

405
~~4545~~ Ft. from N Section Line

330
~~4620~~ Ft. from W Section Line

SEC. 31 TWP. 31 RGE. 7 (E) or (W)

MAR 08 2004

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR Petroleum Technologies, Inc.

ADDRESS 801 West 47th St. Ste 412 Kansas City Mo 64112 COUNTY Cowley

PHONE(S) (816) 531-6904 OPERATORS LICENSE NO. 8653

Date Well Completed 11/14/74

Character of Well Gas

Plugging Commenced 2/19/04
01/24/04

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/18/04
2/19/04

The plugging proposal was approved on Nov 25, 2003 (date)

by DAVE Williams (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation Cleveland Depth to Top 2410' Bottom 2420' T.O. 2500'
2499'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Cleveland</u>	<u>water</u>	<u>2410</u>	<u>2420</u>	<u>9"</u>	<u>169</u>	<u>0'</u>
<u>Sand</u>			<u>1629</u>	<u>7"</u>	<u>169</u>	<u>0'</u>
<u>Sand</u>			<u>2499</u>	<u>4 1/2"</u>	<u>2499'</u>	<u>1100'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each section.

Sanded Bottom back to 2360' Dumped 4 1/2" cement on top of sand with
Dump Bailer. shot off pipe 1100' Layed out.
Run 1" to 350' inside 7" surface pipe Pumped 9 1/2" cement 4% gel to surface
Pull out 1" pipe top off with cement.

Name of Plugging Contractor Braden Petroleum & Well Plugging Co License No. 32475

Address PO Box 282 Burden, KS 67019

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Technologies Inc.

STATE OF Missouri COUNTY OF Cowley Jackson, ss.

ALAN J. SEATON

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 801 W. 47th St #412, KC, MO 64112

SUBSCRIBED AND SWORN TO before me this 4th day of March 2004, 1904

CELINA M. SANCHEZ
Notary Public - Notary Seal
STATE OF MISSOURI

Celina M. Sanchez
Notary Public

Clay County My Commission Expires:

7/4/04

My Commission Expires: July 4, 2004