

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

Well Plugging Record

K.A.R. -82-3-117

API NUMBER

15-007-22804-0000

LEASE NAME

#1 Forrester

WELL NUMBER

"C"

RECEIVED

MAR 15 2004

TYPE OR PRINT

NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

2440 Ft. from South Line of Section  
330 Ft. from West Line of Section

KCC WICHITA

LEASE OPERATOR National Petroleum Reserves, Inc. SPOT LOCATION 130' N of NW NW SW  
ADDRESS 250 N. Rock Rd, #130 Section 27 Township 33s Range 11w  
CITY, STATE, ZIP Wichita, Kansas 67206 County Barber  
PHONE # 316-681-3515 Date Well Completed August 15, 2002  
Character of Well Dry and Abandoned Date Plugging Commenced August 15, 2002  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed August 15, 2002

The plugging proposal was approved on 03/06/04 (date)  
by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 4725

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	167'			
Redbeds	Shale	167'	265'	8-5/8"	265'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Received plugging orders from Steve Pfeifer on 03/05/04. Plugged on 03/06/04.

Heavy mud in hole and between all plugs. Plugged with total of 125sx 60/40 Poz, 6% Gel.

Bottom plug @ 600' with 50 sx, 2nd plug @ 290' with 50 sx, top plug @ 40' with 10 sx and plugged rathole with 15 sx. No mousehole. Plug down at 1:30 pm on 03/06/04.

Name of Plugging Contractor Sterling Drilling Company

Licence No. 5142

Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: National Petroleum Reserves, Inc. (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott  
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 12th day of March, 2004



Pamela S. Fields  
(Notary Public)

My Commission Expires: 1-28-05

RECEIVED

MAR 15 2004

KCC WICHITA  
**Sterling Drilling Company, Rig #4**

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

**SAMPLE LOG**

**#1 Forrester "C"**

**LOCATION:** 130' N of NW NW SW

Section 27 T 33s R 11w

**API:** 15-007-22804-0000

Barber County, Kansas

**OWNER:** National Petroleum Reserves, Inc.

**COMMENCED:** 26-Feb-04

**CONTRACTOR:** Sterling Drilling Company, Rig #4

**COMPLETED:** 07-Mar-04

**TOTAL DEPTH:** DRILLER 4725 FEET

**Ground Elevation:** 1442

LOGGER 4730 FEET

**KB Elevation:** 1451

**LOG**

0 -	3 FEET	Top Soil
3 -	167 FEET	Surface Sands and Clay
167 -	1760 FEET	Redbeds, Shales and Salt
1760 -	4725 FEET	Limestone, Shale and Dolomite

**CASING RECORDS**

**Surface Casing-8-5/8"**

Spud @ 4:30 pm on 02/26/04. Drilled 12-1/4" hole to 270'. Ran 6 joints of new 20# 8-5/8" surface casing, tally 254' set at 265' KB. Strapped bottom 3 joints, welded next 3 joints. Cemented with 215 sx 60/40 Poz, 2% Gel, 3% CC and 1/4# celloflake per sx. Cement did circulate. Plug down @ 10:30 pm on 02/26/04. By Acid Services, ticket # 7912.

**Plugging Data:**

Received plugging orders from Steve Pfeifer on 03/05/04. Plugged on 03/06/04. Heavy mud in hole and between all plugs. Plugged with total of 125sx 60/40 Poz, 6% Gel. Bottom plug @ 600' with 50 sx, 2nd plug @ 290' with 50 sx, top plug @ 40' with 10 sx and plugged rathole with 15 sx. No mousehole. Plug down at 1:30 pm on 03/06/04. Acid Services ticket #8226. SDC reported plugging to KCC on 03/08/04.

**DEVIATION SURVEYS**

1/2 degree(s) at	270	feet
3/4 degree(s) at	4576	feet