


WELL PLUGGING RECORD

15-147-30183-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Phillips County. Sec. 29 Twp. 1S Rge. 18W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Lawrence Supply Company
Lease Name Goddard Well No. 2
Office Address Box 448 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed January 7, 1951 19
Application for plugging filed December 11, 1953 19
Application for plugging approved December 14, 1953 19
Plugging commenced December 16 19 53
Plugging completed December 19 19 53
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well Oil Feet
3575

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	278'	None
				5-1/2"	3575'	1245'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand from 3575' to 3530' and ran 4 sacks of cement. Set a rock bridge from 278' to 267' and ran 15 sacks of cement. Mudded hole to 40', set a 10' rock bridge and ran 10 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
L. B. Lawrence (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Lawrence Supply Co.
(Signature) Lawrence
Box 448, Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of January, 1954

My commission expires Sept. 15, 1956
Notary Public. Walter J. Volk

24-7368-S 3-53-20M

PLUGGING
FILE DEC 29 1954 R.L.W.
BOOK PAGE 149 LINE 2

RECEIVED
STATE CORPORATION COMMISSION

Jan 30, 1954

POWELL & PETERS DRILLING CO., INC.
 American State Bank Building
 Great Bend, Kansas

15-147-30183-00-00

Ira Goddard No. 2

SW SW SW Sec. 29-1-18
 Phillips County, Kansas

Commenced R. D.: 12-27-50
 Completed R. D.: 1-7-51
 Total Depth: 3575'

Initial Prod:
 Elevation:
 Contractor: Powell and Peters
 Drilling Co., Inc.

Casing: 278' of 8 5/8" 8rd. thd.
 3575' of 5 1/2" 11 1/2 thd. 17#

Strata	Depth
Shale and Sand	0 - 265'
Blue Shale	265 - 310'
Shale and Sand	310 - 520'
Shale and Shells	520 - 1400'
Anhydrite	1400 - 1440'
Red Bed	1440 - 1560'
Red bed and Sand	1560 - 1810'
Lime	1810 - 1845'
Lime and Shale	1845 - 2230'
Shale and Shells	2230 - 2325'
Lime	2325 - 2565'
Shale and Lime	2565 - 2730'
Shale and Shells	2730 - 2895'
Shale	2895 - 3005'
Shale and Shells	3005 - 3163'
Shale and Lime	3163 - 3230'
Lime	3230 - 3296'
Sand	3296 - 3340'
Shale and Shells	3340 - 3369'
Lime	3369 - 3575'

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

POWELL AND PETERS DRILLING CO., INC.

A. R. Peters

A. R. PETERS Vice-Pres.

Signed and sworn to in my presence this 12th day of January, 1951, by A. R. Peters, Vice-President of the POWELL AND PETERS DRILLING CO., INC. a Corporation in the State of Kansas.

Dexter Miner

Notary Public

My Commission expires 9/29/51

