

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-147-00432-00-00

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Phillips County, Sec. 33 Twp. 1 Rge. 18 (E) (W) X

Location as "NE/CNW&SW" or footage from lines C = W/2 NW SW  
Lease Owner Sierra Petroleum Co.  
Lease Name Jackson Well No. #1  
Office Address Box 232, Russell, Kansas 67665  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved 6-4-71 19\_\_\_\_  
Plugging commenced 6-18-71 19\_\_\_\_  
Plugging completed 6-22-71 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3830' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3726'	1288.72'
				8 5/8"	242'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Made bottom hole plug back by pushing plug to 3400', sand from 3400' to 3375'. Mixed and ran 5 sacks cement thru dump bailer.  
Squeezed hole with 5 sacks hulls - 15 sacks gel - 150 sacks cement. Cement from 1200' to 700'. 11 sacks gel, gel from 700' to 250'. Released plug and 25 sacks cement, cement from 250' to 185', 4 sacks gel, gel from 185' to 30'. Displaced with 10 sacks cement - cement from 30' to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 29 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 28 day of June, 1971

My commission expires



Sidney D. Miller  
Notary Public.

15-147-00432-00-00

SIERRA PETROLEUM CO., INC. - Operator

T. D.: 3830'  
Elev.: 2251' B.L.

A. L. JACKSON #1  
QW2 NW SW  
Sec. 33-18-18W  
Phillips County, Kansas

Commenced: 11-20-63  
Completed: 11-30-63

Casing:

5-5/8" Set at 242'  
5-1/2" Set at 3715.35'

Cement:

with 175 sx. Pozmix  
with 175 sx. Pozmix  
Salt Saturated

FORMATION

Surface Clay & Sand  
Shale  
Shale & Shells  
Shale & Shells w/ Sand Streaks  
Sand  
Shale  
Shale & Shells  
Anhydrite  
Shale & Shells  
Red Bed  
Red Bed & Shale  
Shale & Lime  
Lime  
Lime & Shale  
Lime  
Shale & Shells  
Lime w/ Chert  
Lime

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 4 1971  
CONSERVATION DIVISION  
Wichita, Kansas

DEPTH

200  
242  
310  
1120  
1525  
1565  
1710  
1745  
1760  
2020  
2160  
3251  
3333  
3405  
3652  
3672  
3720  
3830

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

C. T. Hendrix  
Drilling Superintendent

Subscribed and sworn to before me this 2nd day of December, 1963.

Leroy Dantz  
Notary Public

My commission expires: 10-17-67