


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-147-00758-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Phillips County. Sec. 33 Twp. 15 Rge. 18W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW SW SW

Lease Owner Lawrence Supply Company

Lease Name Jackson Well No. 2

Office Address 1306 Cleveland - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 9/11/50 19

Application for plugging filed 1/10/53 19

Application for plugging approved 1/10/53 19

Plugging commenced 1-12-53 19

Plugging completed 1-14-53 19

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation K.C. Depth to top Bottom Total Depth of Well 3544 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
K.C.				5-1/2"	3544'	1118'
				8 5/8"	187'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole from 3544' to 3520' and ran 4 sacks of cement. Checked mud to 187'. Set rock bridge from 187' to 179' and ran 15 sacks of cement. Mudded hole to 35', set rock bridge to 28' and ran 10 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
L. B. Lawrence

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. B. Lawrence

Box 448, Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of March, 1953

My commission expires Sept 26, 1956

24-2675-S 2-52-20M

PLUGGING
FILE SEC 33 T 1 R 18W
BOOK PAGE 23 LINE 45

CONSERVATION DIVISION
Wichita, Kansas

march 7, 1953

15-147-00758-00-00

Box 448
March 6, 1933

~~Kansas Well Log Bureau
508 East Murdock
Wichita, Kansas~~

Gentlemen:

Enclosed is stamped and addressed envelop, also, check for \$.25 to cover well log. It would be very much appreciated if you would send copy of well log on Jackson No. 2, NW SW SW of Sec. 33-1S-18W, Phillips County, to the State Corporation Commission.

Yours very truly

LAWRENCE SUPPLY CO.

By *L. B. Lawrence*
L. B. Lawrence

2/16/66

*Called Kansas Well Log B.
log is not available
BH*

CC: Mr. J. P. Roberts ✓
State Corporation Comm.
Conservation Div.
800 Hitting Bldg.
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR - 7 1933

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 33 T 1 R 18W
BOOK PAGE 73 LINE 45