


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-147-00985-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Phillips County. Sec. 33 Twp. 15 Rge. 18 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Lawrence Supply Company
Lease Name Jackson Well No. 1
Office Address 1306 Cleveland - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 7/1 1950
Application for plugging filed 1/10 1953
Application for plugging approved 1/10 1953
Plugging commenced 1-15 1953
Plugging completed 1-18 1953
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation K.C. Depth to top _____ Bottom _____ Total Depth of Well 3540 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>K.C.</u>				<u>5-1/2"</u> <u>8 5/8"</u>	<u>3540'</u> <u>180'</u>	<u>2181'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran 5 sacks of cement on bottom. Mudded hole to 180', set 10' rock bridge and ran 15 sacks of cement. Mudded hole to 35', set 10' rock bridge and ran 10 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
L. B. Lawrence, owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

By L. B. Lawrence (Signature)
Lawrence Supply Co.
L. B. Lawrence
Box 443 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 6 day of March, 1953
G. P. Johnson Notary Public.

My commission expires Sept 26, 1956

24-2675-S 2-52-20M

PLUGGING
FILE SEC 33 T 1 R 18 W
BOOK PAGE 74 LINE 1

CONSERVATION DIVISION
Wichita, Kansas
March 7, 1953

15-147-00985-00-00

LAWRENCE SUPPLY COMPANY
BOX 448
GREAT BEND, KANSAS

WELL LOG: Jackson #1, NW NW SW Sec. 33-1S-18W, Phillips County, Kansas

Surface Casing: 8-5/8", circ. @ 180'
Oil String: 5-1/2", set @ 3540' w/ 125 sacks
Top Anhydrite: 1765'
" Topeka: 3176'
" Heebner: 3396'
" Lansing-KC: 3423'
Total Depth: 3540'

RECEIVED
STATE CORPORATION COMMISSION
MAR - 7 1953
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 33 T 1 R 18W
BOOK PAGE 74 LINE 1