

4-041498

7-12

15-147-00730-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 10-51

SW NE NW /4 SEC. 28 , 01 S, 18 W
4290 feet from S section line
3630 feet from E section line

Operator license# 31070

Lease Jackson 'C' well # 2

Operator: Eagle River Energy Corporation County Phillips

Address: 7060 S. Yale
Suite 609
Tulsa, Oklahoma 74136

Well total depth 3500 feet ^{113.75}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 207 feet
w/200 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 12 Month: July Year: 93

Plugging proposal received from: Jerry Rice

Company: Eagle River Energy Corporation Phone:

Were: 5 1/2" casing set @ 3500' w/150 sx. cement. Perfs. @ 3403' - 3410'. Anhy. @ 1700' - Dakota @ 1265'. Junk in hole @ 1760'.
Order 250 sx. 65/35 pozmix - 10% gel. with 1/4# F.C. plus 400# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:30P.M., Day: 12, Month: July, Year: 93

Actual plugging report: R.I.H. with tubing to T.O. fish @ 1760'.
Pumped in 160 sx. cement with 450# hulls to circulate at surface.
P.O.O.H. with tubing. Hooked-up to 5 1/2" casing. Squeezed 50 sx. cement in casing. Max. 200#. S.I.P. 100#. Hooked-up to 10 3/4" S.P.
Pumped in 40 sx. cement with 100# hulls. Max. 200#. S.I.P. 100#.

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did [X] / did not observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1993

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE SEP 14 1993
INV. NO. 38632