

7-12

4-041501

15-147-00732-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - N/A

NW NW /4 SEC. 28, 01 S, 18 W
4620 feet from S section line
4620 feet from E section line

Operator license # 31070 Lease Jackson well # C-4

Operator: Eagle River Energy Corporation County Phillips

Address: 7060 S. Yale Well total depth 3487 feet
Suite 609 Conductor Pipe: 0 inch @ 0 feet
Tulsa, Oklahoma 74136 Surface pipe 8 5/8 Inch @ 208 feet
w/200 sx.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 12 Month: July Year: 93

Plugging proposal received from: Jerry Rice

Company: Eagle River Energy Corporation Phone:

Were: 5 1/2" casing set @ 3487' w/150 sx. cement. Perfs. @ 3340' - 3419'. Anhy. @ 1740' - Dakota @ 1250' - W.L.M. @ 3700' - T.O.F. @ 400'. Order 300 sx. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 8:30P.M., Day: 12, Month: July, Year: 93

Actual plugging report: R.I.H. with tubing to 2700'. Spot 25 sx. cement with 100# hulls. Pull to 1730'. Spot 125 sx. cement with 200# hulls. P.O.O.H. with tubing and squeezed 50 sx. cement with 100# hulls. Hooked-up to 8 5/8" S.P. Squeezed 25 sx. cement. 60/40 pozmix - 10% gel with 100# hulls. Max. 300#. S.I. 200#.

RECEIVED STATE CORPORATION COMM

SEP 13 1993

Remarks: Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: GL CONSERVATION DIVISION
Wichita, Kansas

I did [] observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED
DATE SEP 14 1993
INV. NO. 38630