

4-041656

1-25  
15-147-00983-00-00

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 9-51

SW NW SE /4 SEC. 28 , 01 S, 18 W  
1650 feet from S section line  
2310 feet from E section line

Operator license# 31070

Lease Jackson 'D' well # 1

Operator: Eagle River Energy Corporation

County Phillips

Address: 7060 S. Yale  
Suite #609  
Tulsa, OK 74136

Well total depth 3561 feet <sup>115.73</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 199 feet  
w/125 sxs.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 25 Month: January Year: 95

Plugging proposal received from: Jerry Rice

Company: Eagle River Energy Corporation Phone:           

Were: 5 1/2" casing set at 3561' w/150 sxs. cement. Perfs. at  
3429' - 3553'. Anhy. @ 1840' - Dakota @ 1300' - W.L.M. @ 3500' -  
T.O.F. @ 3100'. Perf. casing at 1840' and 1300'.  
Ordered 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls  
and 8 sxs. gel.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 10:15A.M., Day: 25, Month: January, Year: 95

Actual plugging report: R. U. cementers to pump down 5 1/2" casing with  
25 sxs. cement with 200# hulls, followed with 8 sxs. gel, followed with  
150 sxs. cement and 200# hulls. Max. P.S.I. 500#. S.I.P. 200#.  
Pumped down 10 3/4" S.P. with 50 sxs. cement and 100# hulls mixed in  
cement. Max. P.S.I. 500#. S.I.P. 300#.

Remarks:  
Condition of casing(in hole): GOOD X BAD     Anhy.plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:            GL

I did     observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 07 1995  
CONSERVATION DIVISION  
WICHITA, KANSAS

**INVOICED**  
DATE 2-8-95  
INV. NO. 42184

BD