

4-041502

7-12

15-147-00725-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 10-51

SW SE SW /4 SEC. 28, 01 S, 18 W
660 feet from S section line
3300 feet from E section line

Operator license # 31070 Lease Jackson 'B' well # 1

Operator: Eagle River Energy Corporation County Phillips

Address: 7060 S. Yale Well total depth 3572 feet 116.09
Suite 609 Conductor Pipe: 0 inch @ 0 feet
Tulsa, Oklahoma 74136 Surface pipe 10 3/4 Inch @ 200 feet
w/125 sx.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 12 Month: July Year: 93

Plugging proposal received from: Jerry Rice

Company: Eagle River Energy Corporation Phone:

Were: 5 1/2" casing set @ 3570' w/150 sx. cement. Anhy. @ 1846' -
Dakota @ 1350' - W.L.M. 3500' - T.O.F. @ 2000'.
Order 300 sx. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 4:30P.M., Day: 12, Month: July, Year: 93

Actual plugging report: 5 1/2" casing - pumped in 250 sx. cement with
400# hulls. Max. 300#. S.I. 200#. 10 3/4" S.P. - squeezed 50 sx.
cement with 100# hulls. Max. 400#.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation:

I did not observe the plugging.

INVOICED
DATE SEP 14 1993
INV. NO. 38631

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1993
(agent) Dennis L. Hamel
CONSERVATION DIVISION
Wichita, Kansas
Form CP-2/3