

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00735-00-00
Spot: CSWNENE Sec/Twnshp/Rge: 28-1S-18W
990 feet from N Section Line, 990 feet from E Section Line
Lease/Unit Name: JACKSON E Well Number: 1
County: PHILLIPS Total Vertical Depth: 3485 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATION
Address: 7060 S. YALE #609
TULSA, OK 74136

Conductor Pipe: Size feet: 113.26
Surface Casing: Size 8.625 feet: 190 125 SX CMT
Production: Size 5.5 feet: 3485 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/21/2002 9:00 AM

Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC.

Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (316) 793-2645

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perfs at 3403'-3406'; 3386'-3392'; 3434'-3437'; 3426'-3432'.
T.O.F. at 1625'. Rods & tubing sanded in.
Holes in casing above fish.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/21/2002 11:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing - 1600'+.
Spotted 120 sxs cement with 500# hulls mixed in cement to circulate at surface.
POOH with tubing and squeezed casing with 55 sxs cement.
Max. P.S.I. 800#. S.I.P. 500#.
R.U. Cementers to 8 5/8" S.P. Squeezed 25 sxs cement down annulus.
Max. P.S.I. 500#. S.I.P. 200#.

RECEIVED
DEC 11 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Dennis J. Hamel
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-12-02

INV. NO. 2003060934

DEC 03 2002

0310101

NAT'L ASSOC PET #1 JACKSON E 28-1-18W 6
SW NE NE
Contr. FERRELL DRILLING CO PHILLIPS County

E 2159 RB Comm. Comp. 11-30-51 IP 176 BOPD (KC)
PHY: POT

Tops	Depth	Datum
LANS	3332	-1173
T.D.	3485	-1326

Casing
8" 190 PERF 12 S 3403-06
5" 3485 24 S 3386-92
ACID 1000: 8 BOPH

HUFFSTUTTER POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS