

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

RECEIVED  
MAR 15 2004  
KCC WICHITA

130 S. Market, Room 2078  
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-007-22804-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: National Petroleum Reserves, Inc.  
(owner/company name)

KCC LICENSE # 9482  
(operator's) 3/04

ADDRESS: 250 N. Rock Rd, #130 CITY: Wichita

STATE: Kansas ZIP CODE: 67206 CONTACT PHONE: 316-681-3515

LEASE: #1 Forrester WELL#: "C" Section 27 Township 33s Range 11w

130' N of NW NW SW SPOT LOCATION/QQQQ COUNTY: Barber

2440 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)  
330 FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)

Check One: Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ D&A XX SWD/ENHR WELL \_\_\_\_\_ Docket # \_\_\_\_\_  
CONDUCTOR CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS  
SURFACE CASING SIZE 8-5/8" SET AT 265 KB CEMENTED WITH 215 SACKS  
PRODUCTION CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:  
ELEVATION 1442 G.L. 1451 K.B. T.D. 4725 PBDT \_\_\_\_\_ Anhydrite Depth \_\_\_\_\_  
(Stone Corral Formation)  
CONDITION OF WELL: GOOD XX POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING:  
Received plugging orders from Steve Pfeifer on 03/05/04. Plugged on 03/06/04.  
Heavy mud in hole and between all plugs. Plugged with total of 125sx 60/40 Poz, 6% Gel.  
Bottom plug @ 600' with 50 sx, 2nd plug @ 290' with 50 sx, top plug @ 40' with 10 sx and  
plugged rathole with 15 sx. No mousehole. Plug down at 1:30 pm on 03/06/04.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)  
If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:  
Name: Lanny Saloga/Gary Talbott Phone#: (620) 672-9508  
Address: P.O. Box 1006 City: Pratt State: Kansas  
PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142  
(company name) (contractor's) 6/04  
Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 1:00 pm on 03/06/04. Plugged  
PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent \_\_\_\_\_

DATE: 03/07/04 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott  
(signature) Gary M. Talbott, Agent for Operator

# Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

## SAMPLE LOG

#1 Forrester "C"

**LOCATION:** 130' N of NW NW SW Section 27 T 33s R 11w  
**API:** 15-007-22804-0000 Barber County, Kansas

**OWNER:** National Petroleum Reserves, Inc.  
**CONTRACTOR:** Sterling Drilling Company, Rig #4

**COMMENCED:** 26-Feb-04  
**COMPLETED:** 07-Mar-04

**TOTAL DEPTH:** **DRILLER** 4725 FEET  
**LOGGER** 4730 FEET

**Ground Elevation:** 1442  
**KB Elevation:** 1451

### LOG

0 -	3 FEET	Top Soil
3 -	167 FEET	Surface Sands and Clay
167 -	1760 FEET	Redbeds, Shales and Salt
1760 -	4725 FEET	Limestone, Shale and Dolomite

RECEIVED

MAR 15 2004

KCC WICHITA

### CASING RECORDS

#### Surface Casing-8-5/8"

Spud @ 4:30 pm on 02/26/04. Drilled 12-1/4" hole to 270'. Ran 6 joints of new 20# 8-5/8" surface casing, tally 254' set at 265' KB. Strapped bottom 3 joints, welded next 3 joints. Cemented with 215 sx 60/40 Poz, 2% Gel, 3% CC and 1/4# celloflake per sx. Cement did circulate. Plug down @ 10:30 pm on 02/26/04. By Acid Services, ticket # 7912.

#### Plugging Data:

Received plugging orders from Steve Pfeifer on 03/05/04. Plugged on 03/06/04. Heavy mud in hole and between all plugs. Plugged with total of 125sx 60/40 Poz, 6% Gel. Bottom plug @ 600' with 50 sx, 2nd plug @ 290' with 50 sx, top plug @ 40' with 10 sx and plugged rathole with 15 sx. No mousehole. Plug down at 1:30 pm on 03/06/04. Acid Services ticket #8226. SDC reported plugging to KCC on 03/08/04.

### DEVIATION SURVEYS

1/2 degree(s) at 270 feet  
3/4 degree(s) at 4576 feet