

3-24

4-031909

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-147-20,044-00-00

SE NE NE /4 SEC. 22, 01 S, 18 W
4290 feet from S section line
330 feet from E section line

Operator license# 30316 Lease Kent well # 3

Operator: Ronald Jansonius County Phillips

Address: Cougar Energies, Inc. Well total depth 3579 feet
P.O. Box 261 Conductor Pipe: 0 inch @ 0 feet
Oberlin, Kansas 67749-0261 Surface pipe 8 5/8 Inch @ 200 feet

116.31

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License#

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 24 Month: March Year: 94

Plugging proposal received from: Ronald and Dennis Hamel

Company: Cougar Energies, Inc. - KCC Phone:

Were: Order 175 sxs. 60/40 pozmix - 10% gel - 400# hulls.
Perfs - 1765' and 1275'.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:00P.M., Day: 24, Month: March, Year: 94

Actual plugging report: 8 5/8" set at 200' cwc. 5 1/2" set at 3578'.
PBTD 3578' - Prod. Perf. 3328' - 3535'. Squeeze 5 1/2" with 25 sxs.
cement blend with 100# hulls followed with 10 sxs. gel followed with
125 sxs. cement blend with 200# hulls mixed in to Max. P.S.I. 150#.
Close in P.S.I. 150#. Down 8 5/8" with 25 sxs. cement blend with 100#
hulls mixed in to Max. P.S.I. 50#. Close in P.S.I. 50#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation:

RECEIVED

STATE CORPORATION COMMISSION

NO 3-28-1994
MAR 28 1994

I did observe the plugging.

Carl Goodrow
CONSERVATION DIVISION
Wichita, Kansas

(agent)

Form CP-2/3

INVOICED

DATE 4-6-94

INV. NO. 40322

3-24 JUN 02 1994