

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

147
15-~~187~~-20018-00-00

RECEIVED
NOV 2 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Harre of Thoroughbred Drlg. has this date requested permission to plug the following described well:

Mr. Harre guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Co.

Complete Address: 502 Ritz Bldg. Tulsa, Okla.

Lease Name: Oda Hoy Bock "A" Well No. 1

Location: CNW-SW Sec. 35 Twp. 1 Rge. 20 (E)(W) X

County Phillips Total Depth 3840' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Harre was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 990' and displace
100 sc cement thru drill pipe. Heavy mud to 280' set cementing plug and
displace 35 sc cement thru drill pipe. Leave top (210-0) open for fresh
water well. Plug rat hole with 2 sc cement.

Very truly yours,

B. F. Massey
Conservation Division Agent