

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED

MAR 08 2004

KCC WICHITA

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: American Warrior Inc.  
Address: P.O. Box 399 Garden City Ks. 67846  
Phone: (620) 275-2963 Operator License #: 4058

Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 1-21-04 (Date)

by: Scott Alberg (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)  
Mississippian Depth to Top: 5346' Bottom: 5496' T.D. 5575'  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 081-20382 - 00 - 00  
Lease Name: Holloway  
Well Number: #1  
Spot Location (QQQQ): SE - SW - NW  
2970' Feet from  North /  South Section Line  
4290' Feet from  East /  West Section Line  
Sec. 3 Twp. 29 S. R. 32  East  West  
County: Haskell  
Date Well Completed: 10/4/85  
Plugging Commenced: 2/23/04  
Plugging Completed: 2/23/04

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records |         | Casing Record (Surface Conductor & Production) |               |      |               |            |
|---------------------------|---------|--|---------------|------|---------------|------------|
| Formation                 | Content | From   | To            | Size | Put In        | Pulled Out |
| Mississippian             | oil     | Surface  | 1604          | 85/8 | 1604'         | 0          |
|                           |         | Surface  | 5574'<br>5575 | 41/2 | 5574'<br>5575 | 0          |
|                           |         |  |               |      |               |            |
|                           |         |  |               |      |               |            |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed and pumped 30sx plug with hulls down 41/2 casing, Pressured to 2000#. Hooked up to surface head. Mixed and pumped 275 sx cement. Pressured to 400#. Shut in. Cut surface pipe and 41/2 casing off 6' below surface and capped. Back filled.

Name of Plugging Contractor: American Warrior Swi & Services License #: 4058 32382

Address: P.O. Box 399 Garden City Ks. 67846

Name of Party Responsible for Plugging Fees: American Warrior Inc.

State of Ks. County, Finney, ss.

Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 399 Garden City Ks. 67846

SUBSCRIBED and SWORN TO before me this 5 day of March, 20 04

[Signature]  
Notary Public

My Commission Expires: 11/4/07

DEBRA J. PURCELL  
Notary Public - State of Kansas  
My Appt. Expires 11/4/07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202