

RECEIVED
MAR 09 2004
KCC WICHITA

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: ~~Gore Oil Company~~ John O. Farmer

Address: P.O. Box 2757, Wichita, KS 67201-2757

Phone: (316) 263-3535 Operator License #: 5552 5135

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10-10-03 (Date)

by: David P. Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3719' Bottom: 3723' T.D. 3723'

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 137-00,706-00-00

Lease Name: Henry

Well Number: 2

Spot Location (QQQQ): SE - SE - SW -
330 Feet from North / South Section Line

2970 Feet from East / West Section Line

Sec. 35 Twp. 3 S. R. 24 East West

County: Norton

Date Well Completed: 9-20-54

Plugging Commenced: 1-13-04

Plugging Completed: 1-13-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0'	297'	8 5/8"	297'	0'
Production	C	0'	3721'	5 1/2"	3721'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hook up to annulus & pump 45 sx SMD cmt, 200 psi max. Shut in 75 psi. Hook up to tbg & pump 100 sx cmt w/500# hulls.
Cmt circ to pit. Pull tbg out of hole. Hook up to 5 1/2" & pump 65 sx cmt, 700 max psi. Shut in 5 1/2" 300#.
Hook up to 8 5/8" & pump 5 sx cmt. Top off 5 1/2" w/10 sx cmt. Job complete.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382

Address: P.O. Box 466, Ness City, KS 67560-0466


Name of Party Responsible for Plugging Fees: Gore Oil Company

State of Kansas County, Sedgwick, ss.

Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M Jack

(Address) Wichita, KS



SUBSCRIBED and SWORN TO before me this 5th day of March, 20 04

Rebecca K. Crawford My Commission Expires: 3-20-07
Notary Public