

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Anadarko Petroleum Corporation

Address: 1201 Lake Robbins Dr, The Woodlands, TX 77380

Phone: (832) 636-3128 Operator License # 4549

Type of Well: D&A Docket # (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 11/7/03 (Date)

by: Richard Lacey (KCC District Agent's)

Is ACO-1 filed? [x] Yes [] No If not, is well log attached? [] Yes [] No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: Bottom: T.D. 5700

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number 15- 067-21566 700 - 00

Lease Name HJV Bechtelheimer "A"

Well Number 1

Spot Location (QQQQ) N/2 NE NE SW

2640 Feet from [] North / [x] South Line of Section

2225 Feet from [] East / [x] West Line of Section

Sec. 2 Twp. 28 S. R. 37 [] East [x] West

County: Grant

Date Well Completed: N/A

Plugging Commenced: 11/10/03

Plugging Completed: 11/10/03

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put in, Pulled out). Content includes Surface casing, 8-5/8", 1773', None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

Spotted 100 sxs 60/40 POZMIX w/6% gel @ 3000'. Spotted 50 sxs cement @ 1800'. Spotted 40 sxs cement @ 730'. Spotted 10 sxs cement @ 0-10'. 15 sxs in rathole and 10 sxs in mouse hole. Heavy drilling mud was placed between each plug.

RECEIVED KANSAS CORPORATION COMMISSION

MAR 18 2004

Name of Plugging Contractor: Murfin Drilling Co. License # 30606

Address 250 N. Water, Ste 300, Wichita, KS 67202


Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation

State of Texas County, Montgomery, ss.

Jerry N. Blossom (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) [Handwritten Signature] (Address) 1201 Lake Robbins Dr., The Woodlands, TX 77380



Subscribed and SWORN TO before me this 17th day of March, 2004. My Commission Expires: 12-3-05