

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

MAR 16 2004

KCC WICHITA

Form CP-4 December 2003

Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: American Warrior Inc.

Address: P.O. Box 399 Garden City Ks. 67846

Phone: (620) 275-2963 Operator License #: 4058

Type of Well: oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2/24/04 (Date)

by: Jay Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) No Records on file Depth to Top: Bottom: T.D. 384/

API Number: 15 - 051-02835 - 00 - 00

Lease Name: Riedel B

Well Number: 4

Spot Location (QQQQ): C - NE - NW - NW 4950 Feet from North / South Section Line

4290 Feet from East / West Section Line

Sec. 31 Twp. 13 S. R. 19 East West

County: Ellis

Date Well Completed: 4/18/58

Plugging Commenced: 3/9/04 3/8/04

Plugging Completed: 3/9/04 3/8/04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes handwritten entries for Surf Prod at 252' and 3835'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Shot tbg off at 1685'. Pulled tbg out. Perf 1500'2spf and 650'2spf. Ran tbg to 1488'. Pumped 200sx 60/40 posw/10%gel, Cir to pit, Pulled tbg to 744', pumped 35sxn/ 500# hulls, cir cement to surface. pulled tbg. Hooked on to braden head and pumped 20sx down 85/8. 500#. Topped 5' 1/2 off. Cut surface and casing off 6' below GL capped and back filled.

Name of Plugging Contractor: American Warrior Inc. PO Box 19 License #: 4058 6426

Address: P.O. Box 399 Garden City Ks. 67846 Victoria Ks 67627

Name of Party Responsible for Plugging Fees: American Warrior Inc.

State of Kansas County, Finney, ss.

Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

DEBRA J. PURCELL Notary Public, State of Kansas My Appt. Expires 11/4/07

(Signature)

(Address) P.O. Box 399 Garden City Ks. 67846

SUBSCRIBED and SWORN TO before me this 15 day of March 20 04

Handwritten signature of Debra J. Purcell

Notary Public

My Commission Expires: 11/4/07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202