

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-185-10364-0000
API NUMBER ~~15-05/1955~~
LEASE NAME ~~Veeder Dietz~~
Veeder Dietz

WELL NUMBER #5
NOTICE: Fill out **completely**
and return to Cons. Div.
office within 30 days
~~990~~ 986 Ft. from S Section Line
1650 Ft. from E Section Line
1748

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 6 TWP 21S RGE. 11W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY Stafford
PHONE # (316) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 05/1955
Character of Well Oil (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 03/2/04
Plugging Completed 03/2/04

The plugging proposal was approved on 03/2/04 (date)
by Richard Lasey w/KCC in Dodge City, KS (KCC District Agent's Name).
Is ACO-1 filed? No If not, is well log attached? _____
Producing Formation Arbuckle Depth to Top 3442 Bottom 3470 TD3480 Show depth and
thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	260'	8 5/8"	260'	0
		Production	3479	5 1/2"	3479'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows:

Perforated 2 shots per ft. at 600'. TIH w/48 jts 2 3/8" tbg to 1450', 5 1/2" casing. RU Allied cmt. Mix & pumped 25sx 60/40 6% gel w/10 sx gel & 200# hulls, pull 24 jts tbg to 650' mix & pumped 250 sx cmt circ cmt up csg & 8 5/8" surface. TOH w/tbg & top csg. Off. P&A complete @1:30pm. Witnessed by Richard Lasey w/KCC.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606
Address 250 N. Water, Suite 300; Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK .ss.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 15th day of March, 2004

Notary Public - Kristin Grady
My Commission Expires: 2/06/08 Form CP-4



Revised 05-88

RECEIVED
MAR 16 2004
KCC WICHITA

RECEIVED
 MAR 16 2004
 KCC WICHITA

Federal tax I.D.# ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31
 RUSSELL, KANSAS 67665

SERVICE POINT:
Great Bend

DATE <i>3-3-04</i>	SEC <i>6</i>	TWP. <i>21s</i>	RANGE <i>11w</i>	CALLED OUT <i>8:00 am</i>	ON LOCATION <i>10:00 am</i>	JOB START <i>10:45 am</i>	JOB FINISH <i>1:30 pm</i>
LEASE <i>Oiets</i>	WELL # <i>#5</i>	LOCATION <i>South of Ellenwood &</i>		COUNTY <i>Stafford</i>	STATE <i>KS</i>		
OLD OR NEW (Circle one)		<i>city line 2 East - 3 south - West into</i>					

CONTRACTOR *Murfin*
 TYPE OF JOB *Old Hole Plug*
 HOLE SIZE _____ T.D. _____
 CASING SIZE *#5.5* DEPTH *1450*
 TUBING SIZE *2"* DEPTH *1450*
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER *Murfin Drilling Co.*
 CEMENT
 AMOUNT ORDERED *4000 sy 10 1/2 6% gel*
410 sy gel + 200 lbs of balls
used 30.5 sy cement - 10 gel + 50 lbs of ball
 COMMON *183 qt* @ *7.15* *1308.45*
 POZMIX *122 qt* @ *3.80* *463.60*
 GEL *16 qt* @ *10.00* *160.00*
 CHLORIDE _____ @ _____
Hulls 50# @ _____ *9.00*
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 HANDLING *425 qt* @ *1.15* *488.75*
 MILEAGE *425 miles* @ *18* *382.50*

EQUIPMENT

PUMP TRUCK CEMENTER *Jack*
 # *120* HELPER *J. D.*
 BULK TRUCK
 # *342* DRIVER *Steve*
 BULK TRUCK
 # _____ DRIVER _____

TOTAL *2917.15*

REMARKS:

1st plug @ 1450' with 10 sy gel -
27 sy cement with 50 lbs of balls
Pull tubing to 600' surface 200 sy of cement
to circ 2 surface - Pull tubing & Trip
off with 30 sy cement - Pull asg
& Backside circ cement

1 Thanks

SERVICE

DEPTH OF JOB *1450'*
 PUMP TRUCK CHARGE _____ *475.00*
 EXTRA FOOTAGE _____ @ _____
 MILEAGE *18* @ *3.60* *63.00*
 PLUG _____ @ _____
 _____ @ _____
 _____ @ _____

TOTAL \$ *538.00*

CHARGE TO: *Murfin Drilling Co.*
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE *Craig Jack*

PRINTED NAME _____