

15-147-14056-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Phillips County. Sec. 30 Twp. 1 Rge. 18 (E) W (W)
Location as "NE/CNW/SW" or footage from lines ~~NE~~ NE SW
Lease Owner Spector Pipe and Supply Inc.
Lease Name Brockett Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 11-4-58 19
Application for plugging filed Aug. 28, 1966 19
Application for plugging approved Aug. 29, 1966 19
Plugging commenced September 4, 1966 19
Plugging completed September 15, 1966 19
Reason for abandonment of well or producing formation failure to produce profitably
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Kansas City Depth to top 3366 Bottom 3589 Total Depth of Well 3600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	204 ft.	none
				4 1/2" OD	3599 ft.	1400.71

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand to 3350 feet. Filled hole to 3300 and dumped 4 sacks of cement. Circulated mud at 600 feet and dumped 25 sacks cement at 540 feet. Pumped in 20 sacks at 225 feet and put 10 on top.

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lynch Casing Pulling Co. 457
Address R. Rt. 4, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Russell, ss.
Spector Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Ington Spector
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of September, 19 66.

My commission expires December 1, 1968

Elsie Coady
Elsie Coady
Notary Public.

COPY

15-147-19056-00-00
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DON H. PEAKER & LEWIS DRILLING CO.
Farm- Brockett No. 1

SEC. 30 T. 1 R. 18W
NE NE SW

Total Depth. 3600'
Comm. 10-26-58 Comp. 11-4-58
Shot or Treated.
Contractor. Lewis Drig.
Issued. 12-20-58

County Phillips
KANSAS



CASING:

8 5/8" 204'
4 1/2" 3599'

Elevation. 2178' KB

Production. 25 BOPD

Figures Indicate Bottom of Formations.

sand & clay	100
shale	800
shale & sand	1210
sand & pyrite	1330
shale	1360
Dakota sand	1470
red bed & shale	1750
Anhydrite	1780
shale & shells	2090
lime & shale	3380
lime	3420
cherty lime	3460
lime	3512
lime & shale	3530
lime	3600
Total Depth	

TOPS:	
Heebner	3322
Toronto	3350
Lansing-Kansas City	3366
Base Kansas City	3589

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1966
CONSERVATION DIVISION
Wichita, Kansas