

15-147-00416-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Phillips County, Sec. 30 Twp. 1 Rge. 18 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE/4 NW/4 SE/4

Lease Owner Sierra Petroleum Co., Inc.
Lease Name Rakestraw #2 Well No. _____
Office Address Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8/5/80 19____
Plugging completed 8/12/80 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
depleted.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3640
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	212	none
				4 1/2	3640	1212

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3600' and ran 4 sacks cement. Fluid at 300', shot pipe at 1302', 1220', pulled 30 joints of range 3 pipe. Pumped 3 sacks hulls, 8 sacks gel, 70 sacks cement, 10 sacks gel, 2 sacks hulls, 70 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
R. DARRELL KELSO (employee of owner) or _____ (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of August, 19 80

My commission expires _____



Margaret Melcher
Notary Public.

STATE CORPORATION COMMISSION
RECEIVED
AUG 22 1980
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

COMPANY Feldt & Maytag

SEC. 30 T. 15 R. 18W
LOC. SE 1/4 NW 1/4 SE 1/4

FARM Rakestraw

NO. 2


15-147-00416-00-00

TOTAL DEPTH 3640'

COMM. 6-6-59

COMP. 6-15-59

COUNTY Phillips
KANSAS



SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED

ELEVATION 2198 ~~KB~~

PRODUCTION

CASING

20	10
15	$\times 8 \frac{5}{8}'' = 212'$
12	6
13	$\times 4 \frac{1}{2}'' = 3640'$

FIGURES INDICATE BOTTOM OF FORMATIONS

0 -	212	Surface Sand & Clay
212 -	1180	Shale
1180 -	1380	Shale & Shell
1380 -	1495	Dakota Sand
1495 -	1690	Shale & Shell
1690 -	1705	Sand Streak
1705 -	1755	Shale & Shell
1755 -	1765	Shale & Shells
1765 -	1810	Anhydrite
1810 -	2140	Shale & Red Bed
2140 -	3305	Shale & Lime
3305 -	3450	Lime
3450 -	3510	Lime & Shale
3510 -	3563	Lime
3563 -	3640	Lime & Shale
3640 -		Total Depth

Geologic Tops

Heebner	3354
Toronto	3382
Lansing	3398
Base Kansas City	3618

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1960

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED

JUN 22 1959

C. L. F.
J. B. M.

State of Kansas }
County of Sedgwick } ss:

I, William J. Duckett of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Rakestraw #2 well.

Subscribed and sworn to before me this 20th day of June, 1959

My Commission Expires: August 20, 1960

William J. Duckett

A. R. Derrington
NOTARY PUBLIC
(A. R. Derrington)