


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-147-30184-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Phillips County, Sec. 22 Twp. 15 Rge. 18 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C. NE SE SE
Lease Owner Lawrence & Meltzer Oil Co.
Lease Name Kent Well No. 1
Office Address Box 414, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 2/6 19 51
Application for plugging filed 10/3 19 51
Application for plugging approved 10/3 19 51
Plugging commenced 10/20 19 51
Plugging completed 10/23 19 51
Reason for abandonment of well or producing formation Depleted
If a producing well is abandoned, date of last production Sept. 30 19 51
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Kansas City Depth to top 3337' Bottom 3479' Total Depth of Well 3505 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2"		2250'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back w/ crushed rock to 3425'; dumped 4 sacks cement at 3425' w/ dump bailer. Top of cement 3390'. Mudded hole to 178'; set rock bridge, dumped 15 sacks cement. Mudded hole to 35'; set rock bridge; dumped 10 sacks for cap.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lawrence & Meltzer Oil Co.
Address Box 414, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Lawrence & Meltzer Oil Co. (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. LAWRENCE & MELTZER OIL CO.

(Signature)

By *[Signature]*

Box 414, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of November, 19 51.

My commission expires 3/30/53

28-5091-s

8-50

RECEIVED
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

NOV 24 1951

NOV 19 1951

CON. DIVISION
Wichita, Kansas

CON. DIVISION
Wichita, Kansas

Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 E. Murdock Wichita, Kansas


15-147-30184-00-00

Company - HONAKER DRILG. CO., INC.
 Farm - Kent No. 1

SEC. 22 T. 1 R. 18 W
 NE SE SE

Total Depth. 3505
 Comm. 1-10-51 Comp. 3-26-51
 Shot or Treated.
 Contractor. Honaker Drilg. Co., Inc.
 Issued. 9-22-51

County. Phillips
 KANSAS



Elevation. 2157

Production. I.P.P. 20 BO & NW

Figures indicate Bottom of Formations.

surface soil & rock	100
sand	150
shale	178
shale	250
shale & sand	375
shale & shells	590
sand	660
shale	850
shale & shells	1025
sand	1115
shale	1325
sand	1470
sand & shale	1525
shale & shells	1635
shale & red bed	1735
anhydrite	1762
red bed & shale	1870
shale & lime	2175
shale	2243
shale & lime	2620
lime	2710
lime & shale	3165
lime	3505
Total Depth	

Scout Tops:
 Heebner 3308
 Lansing 3337

INDEXING
 FILE NO. 281-1-180
 PAGE 100, LINE 5

RECEIVED
 1951
 OCT 17 1951