

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-20040-00-00
API NUMBER spud 5-25-1968

LEASE NAME Kent "G"

WELL NUMBER #1

3630 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 22 TWP. 1 RGE. 18 ~~W~~

COUNTY Phillips

Date Well Completed 6-15-1968

Plugging Commenced 8-17-1993

Plugging Completed 8-17-1993

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Baird Oil Co., Inc.

ADDRESS Box 428, Logan, KS., 67646

PHONE#(913) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well oil

(Oil Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-17-1993 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation K.C. Depth to Top 3331 Bottom 3552 T.D. 3561

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Sand & loam	water	0	218	8-5/8	218	none
K.C.	oil & water	0	3556	4 1/2	3556	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Mixed 25 sks.cement (60-40 poz 10% gel w/1/4# flo-cel) with 150# hulls followed by 8 sks. gel down the 4 1/2 csq. This followed by 150 sks.cement A/A with 250# hulls down the 4 1/2. Max.press. 300# SI press. 100#. Mixed 25 sks. cement & 100# hulls and pumped between 4 1/2 and 8-5/8

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied License No. N/A

Address Plainville, KS.

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co., Inc. **AUG 23 1993**

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

CONSERVATION DIVISION
Wichita, Kansas

Jim R. Baird (Employee or Operator) (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim R. Baird

(Address) Box 428, Logan, KS., 67646

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 93

Marilyn J. Allen
Notary Public

My Commission Expires: 2-9-94

MARILYN J. ALLEN
State of Kansas
My Appt. Exp. 2-9-94