

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-20077-00-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

API NUMBER _____

LEASE NAME O'NEILL

WELL NUMBER 2

SPOT LOCATION C NW SE

SEC. 22 TWP. 1 RGE. 18 (E) or (W)

COUNTY Phillips

Date Well Completed _____

Plugging Commenced 9/25/85

Plugging Completed 9/25/85

LEASE OPERATOR Twin Eagle Petroleum Corp.

ADDRESS 2431 E. 61st St., Ste 480, Tulsa, OK 74136

PHONE # (918) 745-9143 OPERATORS LICENSE NO. 9058

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? See attached

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Lansing-Kansas City Depth to top 3391 bottom 3508 T.D. 3590

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	195'	0
				4-1/2"	3586'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. See attached

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____
Address P. O. Box 31 Russell, KS 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Thomas C. Mach (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas C. Mach
(Address) 2431 E. 61st St., Ste 480 Tulsa, OK 74136

SUBSCRIBED AND SWORN TO before me this 14th day of October, 1985

STATE OF KANSAS
Notary Public

DEC 23 1985
12-23-85

CONSERVATION DIVISION

My Commission expires: 12-09-85



9/25/85

15-147-20077-00-00

O'Neill #2 Hole in Casing 1150'

Used total of 400 sacks of 60-40 Poz mix with 10% gel, 3% cc, ½ # sack flo cele and 6 sacks of hulls, 20 sacks of gel.

Pumped 50 sacks of cement with hulls down 4½" casing.

Pumped 10 sacks of gel.

Pumped 100 sacks cement with hulls.

Pumping press 1000 PSI

Shut in press 300 PSI

Pumped 100 sacks cement with hulls down 8 5/8 casing.

Pumped 10 sacks of gel.

Pumped 100 sacks cement with hulls down 8 5/8 casing.

Pumping press 500 PSI

Shut in press 300 PSI

Well plugged 10:45 a.m.

The plugging was witnessed by Dennis Hammel with the Kansas Corporation Commission.

STATE CORPORATION COMMISSION

DEC 23 1985

CONSERVATION DIVISION
Wichita, Kansas