

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-137-20,366-00-00

LEASE NAME May-Mongelli

WELL NUMBER 1

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 27 TWP. 1S RGE. 21W (E) or (W)

COUNTY Norton

Date Well Completed 12-10-86

Plugging Commenced 12-10-86

Plugging Completed 12-10-86

LEASE OPERATOR Kodiak Petroleum

ADDRESS 6060 S. Willow Dr., Suite 2110, Englewood, CO 80111

PHONE# (303) 779-4454 OPERATORS LICENSE NO. 9971

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Harvey Moore, Kodiak notified.

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD CL

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8-5/8"	215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

1st plug @ 3760' w/ 20 sx; 5th plug @ 40' w/10 sx;

2nd plug @ 1920' w/ 20 sx; 10 sx in rat hole.

3rd plug @ 1160' w/100 sx;

4th plug @ 265' w/ 40 sx;

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033

Address 250 N. Water, Suite 300, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Rob Ramseyer

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Rob Ramseyer, Agent for Operator

250 N. Water, Suite 300


Wichita, KS 67202

Wichita, KS 67202

day of December, 19 86

Eleanor Hall

Notary Public



SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 86

Commission Expires: 4-25-87

JAN 14 1987
1-14-87
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84

120 Day

Steve Carlton

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date ... November 15, 1986 ... month day year

API Number 15- 137-20,366-00-00

OPERATOR: License # 9971 Name Kodiak Petroleum, Inc. Address 6060 S. Willow Dr., Suite 2110 City/State/Zip Englewood, Colorado 80111 Contact Person Kent A. Johnson Phone (303) 779-4454

SW SW. SW. Sec. 27. Twp. 1 S, Rg. 21 West 330 Ft. from South Line of Section 4950 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet County Norton

Lease Name May-Mongelli Well # 1-27 Ground surface elevation 2235 feet MSL

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

Depth to bottom of fresh water 180' Depth to bottom of usable water 1150'

Surface pipe by Alternate: 1 2 X Surface pipe planned to be set 200' B. 5/8"

Conductor pipe required Projected Total Depth 3800 feet

Formation Granite Wash

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus essentially plugging hole to KCC specifications.

Date 11/7/86 Signature of Operator or Agent Title President

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt.

This Authorization Expires 5-10-87 Approved By 11-10-86

Start Dec. 6

Hawley City

Handwritten initials and signatures

Sec. Twp. S, Rg. West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 40 feet depth with 10 sx of 60-40 POZ. 2nd plug @ 280 feet depth with 40 sx of 60-40 POZ. 3rd plug @ 1180 feet depth with 100 sx of 60-40 POZ. 4th plug @ 1900 (Anhydrite) feet depth with 25 sx of 60-40 POZ. 5th plug @ 3735 (Arbuckle) feet depth with 25 sx of 60-40 POZ. (2) Rathole with 15 sx (b) Mousehole with 10 sx

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging. In Addition: Call district office after well is either plugged or production casing is cemented in.

(Call 7 a.m. to 5 p.m. workdays)

District office use only:

API #15- 137-20,366 Surface casing of feet set with sx at hours Hays, KS Alternate 1 or 2 surface pipe was used. Alternate 2 cementing was completed @ ft. depth with sx on Hole plugged 19, agent

RECEIVED KCC DIST. #6 Hays, KS

NOV 12 1986 DEC 15 1986

STATE CORPORATION COMMISSION CONSERVATION DIVISION Wichita, Kansas