

RECEIVED  
MAR 03 2004  
KCC WICHITA

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15- 175-20943 - 00 - 00 <sup>01</sup> (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

Indicate original spud or completion date \_\_\_\_\_

Well Operator: Anadarko Petroleum Corporation KCC License #: 4549

Address: 1201 Lake Robbins Drive (Owner/Company Name) City: The Woodlands (Operator's)

State: TX Zip Code: 77380 Contact Phone: 832 636-3127

Lease: Etzold Unit South Well #: 5-2 Sec. 27 Twp. 33 R. 34  East  West

C NW Spot Location/QQQQ County Seward

1370 Feet from (in exact footage)  North /  South (from nearest outside section corner) Line of Section (not Lease Line)

1320 Feet from (in exact footage)  East /  West (from nearest outside section corner) Line of Section (not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # E-24,960  Other \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8 Set at: 1640 Cemented with: 775 Sacks

Production Casing Size: 5-1/2 Set at: 6409 Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs 6262-6302

Elevation: 2907.7 ( G.L.  K.B.) T.D. 6410 PBTD 6372 Anhydrite Depth ----  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): See Attached

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

List Name of Company Representative authorized to be in charge of plugging operations:

John Shilling Phone: 620 482-1005

Address: 1701 W. 2nd St City/State Liberal, KS 67901

Plugging Contractor Sargent & Horton Plugging, Inc. KCC License # 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731 Phone: 405 854-6515

Proposed Date and Hour of Plugging (If known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2/24/04 Authorized Operator / Agent: Jim LaFevers

Jim LaFevers (Signature)

**PLUG AND ABANDONMENT PROCEDURE**

*15-175-20943-00-00*

**WELL NAME:**  
**SPOT:**  
**LOCATION:**  
**COUNTY, ST:**  
**FIELD:**

**ETZOLD UNIT SOUTH 5-2**  
C NW/4  
27-33S-34W  
SEWARD, KS  
ETZOLD UNIT SOUTH

**Charge to:**  
**TD:** 6410' **PBTD:** 6372'  
**GL Elev:** 2908'  
**APC WI:** .1.0000  
**APC RI:** 0.87500

**Tubulars:**

Surface Casing: 8-5/8", 24#, @ 1640'  
Production Casing: 5-1/2", 15.5# @ 6409'  
Tubing 2-3/8", 4.7# @ 6190' & Baker Loc-Set PKR.

**Status:**

Currently TA'd

**Objective:**

P&A

1. Notify KCC District office at least 5 days prior to operations (620.225.8888).
2. MIRU pluggers.
3. Release PKR and TOH with 2-3/8" tbg and PKR.
4. Dump 2 sxs hulls and 30 sxs Class H Neat (1.06 yield, 16.4 ppg, 5.7 bbl) cmt to plug from 6372' to 6200'.
5. Load hole with 9 ppg mud.
6. RU Jacks and measure stretch. Shoot off 5-1/2" csg @ +/- 1740'.
7. Using 5-1/2" csg spot 50 sxs Class H Neat (1.06 yield, 16.4 ppg, 9.4 bbl) cmt from 1700' to 1550' using balanced plug method.
8. TOH with 5-1/2" csg to 700' keeping hole loaded with 9 ppg mud.
9. Using 5-1/2" csg spot 50 sxs Class H Neat (1.06 yield, 16.4 ppg, 9.4 bbl) cmt from 700' to 550' using balanced plug method.
10. TOH with 5-1/2" csg to 40' keeping hole loaded with 9 ppg mud.
11. Using 5-1/2" csg spot 15 sxs Class H Neat (1.06 yield, 16.4 ppg, 2.8 bbl) cmt from 40' to 4' using balanced plug method.
12. TOH with remaining 5-1/2" csg.
13. Cut off & cap 8-5/8" csg 4' below GL w/ 1/4" steel cap (w/ weep hole) w/ following inscription on cap:

APC EUS 5-2  
Sec. 27-33S-34W  
API# 15-175-20943  
Plugged (Date?)

**RECEIVED**  
**MAR 03 2004**  
**KCC WICHITA**

14. RDMO. Restore location.

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Anadarko Petroleum Corporation  
1201 Lake Robbins Drive  
The Woodlands, TX 77380

March 08, 2004

Re: ETZOLD UNIT SOUTH #5-2  
API 15-175-20943-00-00  
NW 27-33S-34W, 1370 FNL 1320 FWL  
SEWARD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely

David P. Williams  
Production Supervisor